

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							350				350		CY	COMMON EXCAVATION	203.15				
									200		200		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									225		225		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
									425		425		CY	COFFERDAM EXCAVATION, EARTH	208.30				
									60		60		CY	COFFERDAM EXCAVATION, ROCK	208.35				
									1		1		LS	COFFERDAM	208.40				
							300				300		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
														BEGIN OPTION AA					
							275				275		CY	SUBBASE OF GRAVEL	301.15				
							275				275		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25				
							275				275		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
														END OPTION AA					
							3				3		CWT	EMULSIFIED ASPHALT	404.65				
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
									95		95		SY	SHEET MEMBRANE WATERPROOFING, SPRAY APPLIED	520.10				
									2		2		EACH	REMOVAL OF STRUCTURE (5'-0" RCP)	529.15				
									1		1		LS	PRECAST CONCRETE STRUCTURE (10'-0" x 8'-0" x 7'-8" BOX)	540.10				
								1			1		MGAL	DUST CONTROL WITH WATER	609.10				
									5		5		CY	STONE FILL, TYPE II	613.11				
									250		250		CY	STONE FILL, TYPE III	613.12				
							2				2		EACH	STEEL MARKER POSTS	619.16				
							54				54		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215				
							200				200		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.217				
							2				2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							50				50		LF	REMOVE AND RESET GUARDRAIL	621.75				
							250				250		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
									110		110		TON	CRUSHED STONE BEDDING	629.54				
							200				200		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										2000	2000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							450				450		LF	4 INCH WHITE LINE	646.20				
							450				450		LF	4 INCH YELLOW LINE	646.21				
									330		330		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
									350		350		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								90			90		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								85	25		110		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				

PROJECT NAME: ADDISON
PROJECT NUMBER: STP CULV(14)
FILE NAME: s08b062qnt.dgn
PROJECT LEADER: K. HIGGINS
DESIGNED BY: J. SALVATORI
QUANTITY SHEET 1
PLOT DATE: 09-MAR-2013
DRAWN BY: J. GRIGAS
CHECKED BY: J. SALVATORI
SHEET 4 OF 28