

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	TRAINING	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
														BEGIN OPTION EE					
							53				53		LF	36" RCP CLASS III	601.0845	--			
							53				53		LF	36" CPEP(SL)	601.2630	--			
														END OPTION EE					
														BEGIN OPTION FF					
							133				133		LF	42" RCP CLASS III	601.0850	--			
							133				133		LF	42" CPEP(SL)	601.2635	--			
														END OPTION FF					
							34				34		LF	18" CPEP(SL)	601.2615	--			
							77				77		LF	24" CPEP(SL)	601.2620	--			
							47				47		LF	36" CPEP(SL)	601.2630	--			
							17				17		EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20	--			
							1				1		EACH	PRECAST REINFORCED CONCRETE MANHOLE WITH CAST IRON COVER	604.21	--			
							2				2		EACH	PRECAST REINFORCED CONCRETE PIPE DI WITH CAST IRON GRATE	604.25	--			
							1				1		EACH	CAST IRON GRATE WITH FRAME, TYPE A	604.45	--			
							1520				1520		LF	6 INCH UNDERDRAIN PIPE	605.10	23			
							80				80		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	12			
							14				14		EACH	UNDERDRAIN FLUSHING BASIN	605.95	--			
							160				160		HR	ROADWAY PATROL MAINTENANCE	607.10	--			
							331				331		MGAL	DUST CONTROL WITH WATER	609.10	3			
							10				10		CY	STONE FILL, TYPE I	613.10	EST.			
							50				50		CY	STONE FILL, TYPE II	613.11	1			
							1270				1270		LF	VERTICAL GRANITE CURB	616.21	15			
							1				1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	--			
							24				24		EACH	STEEL MARKER POSTS	619.16	--			
							550				550		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	12.5			
							1				1		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	--			
							1				1		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	--			
							464				464		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	--			
							505				505		LF	TEMPORARY TRAFFIC BARRIER	621.90	--			
							255				255		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95	--			
							600				600		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							1600				1600		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	--			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	--			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	--			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	--			
								520			520		HR	EMPLOYEE TRAINEESHIP	634.10	--			
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	--			
							1				1		LS	TRAFFIC CONTROL	641.10	--			

PROJECT NAME: HYDE PARK  
 PROJECT NUMBER: HES 030-2(23)  
 FILE NAME: t08b126frm.dgn PLOT DATE: 03-JAN-2011  
 PROJECT LEADER: JLS DRAWN BY: MBL  
 DESIGNED BY: MBL CHECKED BY: JAD  
 QUANTITY SUMMARY SHEET 2 SHEET 6 OF 100