STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 2.0 lb/ft 2.16	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMAINED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
T.H. 5		1	36	36	9.00																													W2-6		SHSM
STA. 60+50.0, RT.		1	36	36	9.00						2					X		X															W3-2		SHSM
		1	18	18	2.25																												W13-1		SHSM
STA. 61+25.53, LT.		1	30	30	6.25						2					X		X															W3-5		SHSM
STA. 62+52.1, CL.		1	24	30	5.00						1					X		X	X														R4-7		SHSM
		1	18	18	2.25																												OMI-1		SHSM
STA. 62+52.1, LT.		1					1																										SALVAGE TOWN SIGN WITH POST		
STA. 62+85.5, RT.		1	36	36	9.00						1					X		X															RI-2		SHSM
STA. 62+89.9, LT.							1				1					X		X	X														SALVAGE SIGNS ON NEW POSTS		E-123
STA. 62+92.0, RT.		1	36	36	9.00						1					X		X	X														RI-2		SHSM
TOTAL TSS SHEET 1					89.88	114.00										195			2									2		296	W 6x15				
TOTAL TSS SHEET 2					100.63											225			5																
TOTAL TSS SHEET 3					105.44	114.00										210			1									2		221	W 6x15				
TOTAL TSS SHEET 4					85.69	99.13										135			2									2		240	W 6x15				
TOTAL TSS SHEET 5					51.75		2									120			3																
ROUNDING					0		0									0			0									0		0					
												FT	FT	FT	FT	FT 885	FT		EA 13	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 433.39	SF 327.13	EA 2	SF				FT			FT 885				LB	EA	LB						EA 6	EA	LB 757					

SHSM = 2010 FHWA'S STANDARD HIGHWAY SIGNS & MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HYDE PARK
PROJECT NUMBER: HES 030-2(23)

FILE NAME: t08bl26frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: MBL
TRAFFIC SIGN SUMMARY SHEET 5

PLOT DATE: 21-DEC-2010
DRAWN BY: MBL
CHECKED BY: JAD
SHEET 49 OF 100