QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

GOV'T NON-PARTIC.	FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				3	3	EA	THINNING AND TRIMMING FOR SIGNS	201.31	EST.
				3750	**3750**	CY	COMMON EXCAVATION ⚠	203.15	**56**
				5350	5350	CY	SOLID ROCK EXCAVATION	203.16	7.1
				75	75	CY	EARTH BORROW	203.30	EST.
				1750	1750	CY	TRENCH EXCAVATION OF EARTH	204.20	37.5
				25	25	CY	TRENCH EXCAVATION OF ROCK	204.21	EST
				1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
				43000	43000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	519.1
				14400	14400	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	37.1
				12350	12350	TON	SUBBASE, RAP	301.40	23.0
				34500	34500	SY	RECLAIMED STABILIZED BASE	310.20	271.0
				1025	1025	TON	AGGREGATE SHOULDERS	402.12	16.0
				1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
				610	610	CWT	EMULSIFIED ASPHALT, COLD MIX	415.25	4.0
				8700	8700	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	35.4
				1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
				1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
				1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
				1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
				10	10	LF	18" CPEP (SL)	601.2615	-
				2	2	EA	CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.10	-
				10	10	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.
				2	2	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.
				1	1	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	EST.
				5800	5800	LF	6 INCH UNDERDRAIN PIPE	605.10	20.2
				150	150	LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	30.0
				25	25	EA	UNDERDRAIN FLUSHING BASIN	605.95	1
				310	310	HR	POWER GRADER RENTAL	608.15	EST
				620	620	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
				110	110	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
				60	60	HR	POWER BROOM RENTAL TYPE II	608.31	EST
				1240	1240	HR	TRUCK RENTAL	608.37	EST
				310	310	HR	LOADER RENTAL, TYPE I	608.40	EST
				1530	1530	MGAL	DUST CONTROL WITH WATER	609.10	7.5
				1300	1300	CY	STONE FILL, TYPE I	613.10	12.5
				160	160	LF	REMOVAL OF EXISTING CURB	616.41	7.0

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
41345.6	SY	VT ROUTE 105
1135.3	SY	SIDE ROADS
519.1	SY	ROUNDING
43000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT TYPE IVS
		WEARING COURSE
6314.3	TON	TYPE IVS
		SIDEROAD APRONS
130.7	TON	TYPE IVS
		PULL OFFS
58.0	TON	TYPE IVS
		PARKING AREAS
20.7	TON	TYPE IVS
		LEVELING COURSE
2140.9	TON	TYPE IVS
35.4	TON	ROUNDING
8700	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

REVISION	BY	DATE
⚠	KML	9-27-2011

REVISION NO.1- REVISED QUANTITY OF ITEM 203.15

PROJECT NAME: NEWPORT-COVENTRY-NEWPORT
PROJECT NUMBER: STP 2802(I)

FILE NAME: IPARM.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 08b158-10.1

PLOT DATE: 27-SEP-2011
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 10 OF 134