

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
									250		250		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									180		180		CY	STRUCTURE EXCAVATION	204.25				
									75		75		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
									22		22		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
									1200		1200		SF	TEMPORARY STEEL SHEET PILING	505.36				
									2460		2460		LB	REINFORCING STEEL	507.15				
									2		2		GAL	WATER REPELLENT, SILANE	514.10				
									1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
									30		30		CY	CONCRETE, CLASS D	541.31				
									230		230		CY	STONE FILL, TYPE III	613.12				
							25				25		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
							1				1		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50				
							50				50		LF	REMOVE AND RESET GUARDRAIL	621.75				
							63				63		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							40				40		HR	FLAGGERS	630.15				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
								250			250		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								280			280		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								10			10		LB	SEED	651.15				
								100			100		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								30			30		CY	TOPSOIL	651.35				
								230			230		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								80			80		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								350			350		SY	TEMPORARY EROSION MATTING	653.20				
								150			150		SY	PERMANENT EROSION MATTING	653.21				
								10			10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								40			40		CY	VEHICLE TRACKING PAD	653.35				
								1			1		EACH	FILTER BAG	653.45				
								450			450		LF	BARRIER FENCE	653.50				
							1				1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
							2				2		EACH	TEMPORARY DETECTOR	678.42				
									90		90		CY	SPECIAL PROVISION (STONE FILL, STREAM BED MATERIAL)	900.608				

PROJECT NAME: WINHALL
PROJECT NUMBER: STP CULV(22)
FILE NAME: ...drawing\z08bl98qty.dgn PLOT DATE: 1/5/2011
PROJECT LEADER: G. BOGUE DRAWN BY: J. SOTER
DESIGNED BY: T. KNIGHT CHECKED BY: M. CHENETTE
QUANTITY SHEET 1 SHEET 5 OF 21

