



REMOVE AND DISPOSE OF END OF EXISTING CMPPA UNDER ITEM 529.20

REMOVE AND DISPOSE OF END OF EXISTING CMPPA UNDER ITEM 529.20

IMPACT SUMMARY



TEMPORARY IMPACTS BELOW OHR: 570 SF



PERMANENT IMPACTS BELOW OHR: 2200 SF

TOTAL IMPACTS: 2770 SF

LEGEND

- ORDINARY HIGH WATER
- ITEM 900.608 SPECIAL PROVISION (STONE FILL, STREAM BED MATERIAL)
- 3'-0" STONE FILL, TYPE III
- LIMITS OF SOIL DISTURBANCE
- ITEM 505.36, TEMPORARY STEEL SHEET PILING



NOTES

1. APPROXIMATE R.O.W. SHOWN USING RECORD CONSTRUCTION PLANS.
2. FOR ROCK WEIR DETAILS SEE SHEET 16.
3. REMOVE DAMAGED QUORRAL AND REPLACE WITH NEW STEEL BEAM QUORRAL AND MANUFACTURED TERMINAL SECTION (FLARED AS DIRECTED BY THE ENGINEER. PAYMENT WILL BE MADE UNDER ITEMS 624.04 AND 625.05).
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY ACCESS TO CULVERT INLET AND OUTLET. PAYMENT WILL BE MADE UNDER ITEM 900.645, "SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT); ALL RESULTING DISTURBED EARTH SHALL BE STABILIZED AND RESTORED UPON COMPLETION OF CONSTRUCTION.
5. THE CONTRACTOR SHALL DESIGN AND IMPLEMENT A TEMPORARY STREAM DIVERSION IN ACCORDANCE WITH ITEM 900.645 SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM).
6. SEE SHEET 3 FOR ALIGNMENT PLAN.
7. REMOVE AND RESET QUORRAL AS NECESSARY TO INSTALL TEMPORARY SHEET PILING. PAYMENT WILL BE MADE UNDER ITEM 624.75, REMOVE AND RESET QUORRAL.

PROJECT NAME: WINHALL
PROJECT NUMBER: STP CULV(22)

FILE NAME: \\s:\proj\2200\09\99\plan.dgn
DESIGNED BY: T. KNIGHT
LAYOUT

PLOT DATE: 1/20/2011
DRAWN BY: J. SOTER
CHECKED BY: M. CHENETTE
SHEET 7 OF 21