

GENERAL NOTES

1. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE STATE OF VERMONT AGENCY OF TRANSPORTATION (VTRANS) STANDARD SPECIFICATIONS FOR CONSTRUCTION, DATED 2006 AND ITS LATEST REVISIONS AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), DATED 2003 AND ITS LATEST REVISIONS.
2. ALL SIGNS WITHIN THE PROJECT LIMITS ARE TO BE REPLACED UNLESS OTHERWISE NOTED OR AS DIRECTED BY THE RESIDENT ENGINEER. ALL NEW SIGNS SHALL BE IN ACCORDANCE WITH THESE PLANS, THE CURRENT MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE STANDARD HIGHWAY SIGN BOOK, APPLICABLE VTRANS E-SERIES STANDARDS OR AS DIRECTED BY THE RESIDENT ENGINEER. SIGN LOCATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. EXACT LOCATIONS TO BE DETERMINED BY THE RESIDENT ENGINEER IN THE FIELD.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE TO PRIVATE OR PUBLIC PROPERTY BEYOND THAT SHOWN ON THE PLANS CAUSED BY THE CONTRACTOR, AT THE SOLE COST OF THE CONTRACTOR.
4. ALL FORMED 2" SQUARE STEEL SHAPED POSTS SHALL BE FABRICATED WITH 12 GAUGE STEEL WITH A MINIMUM YIELD OF 55 KSI. NO FLANGE CHANNEL SUBSTITUTIONS WILL BE ALLOWED.
5. ALL REMOVED SIGNS AND POSTS FROM THIS PROJECT SHALL BE STOCKPILED AT THE VERMONT AGENCY OF TRANSPORTATION- DISTRICT 5 WILL ACCEPT ALL SALVAGED SIGNS AND POST THAT ARE REUSABLE. THE CONTRACTOR MUST SCHEDULE DELIVERY OF THE SALVAGED SIGNS AND POSTS DURING NORMAL WORK HOURS, 07:30 A.M. TO 3:30 P.M. WITH THE AREA SUPERVISOR, EUGENE ALLEN 802-388-2003. THE CONTRACTOR WILL BE RESPONSIBLE TO OFF LOAD THE DELIVERY TRUCK AT THE MARKED LOCATION AT THE MIDDLEBURY GARAGE DURING NORMAL WORKING HOURS. SEE THE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

PROJECT NAME: SUDBURY-MIDDLEBURY
PROJECT NUMBER: STPG SIGN (16)

FILE NAME: stp sign16 cover.dgn PLOT DATE: 22-JUL-2014 16:44
PROJECT LEADER: N. AVERY DRAWN BY: ROADWAY
DESIGNED BY: N. AVERY CHECKED BY: A. GAMBLE
GENERAL NOTES SHEET 3 OF 45