# TRAFFIC SIGN SUMMARY SHEET

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | EXIST POST SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) lb/ft 2.0 | 2.0 | 2.5 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft 3.0 | 4.0 | 4.0 MOD | TUBULAR STEEL Ø (in) FOUND-ATION | lb/ft 3.0 | 3.5 | 4.0 | 5.0 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | 1.3 | 1.7 | 1.7 | 7.6 | 9.0 | 10.8 | 14.6 | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | |
| 291+26 LT<br>STA. 291+26.00, LT.<br>291+66 LT | STOP<br>LLL 24,000 | | | | 5.0 | | X | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| STA. 291+88.00, LT. | EAST SOUTH WEST<br>VERMONT VERMONT VERMONT | 3<br>3<br>3 | 24<br>24<br>21 | 12<br>24<br>15 | 6.00<br>12.00<br>6.57 | | | | 2 | | | | | | | | | | | | | | | | | | | | | | #3 | M3-2 M3-3 M3-4<br>MI-5 MI-5 MI-5<br>M6-1 M6-3 M6-3 | | E-123<br>E-136B<br>E-136B<br>E-136B |
| STA. 294+31.00, RT. | WHITING<br>MIDDLEBURY<br>NORTH<br>VERMONT | 2<br>1<br>1 | 72<br>24<br>24 | 12<br>12<br>24 | 12.00<br>2.00<br>4.00 | | | | 1<br>X | | ~~2~~ | | | | | | ~~X~~ | | | | | | | | | | | | | | | | D2-1<br>M3-1<br>MI-5 | | E-123<br>E-136B<br>E-136B |
| STA. 294+84.00, LT. | SUDBURY<br>CASTLETON CORS<br>BRANDON | 3 | 72 | 12 | 18.00 | | | | 2 | | ~~2~~ | | | | | | ~~X~~ | | | | | | | | | | | | | | | | DI-1A<br>DI-1A<br>DI-1A | | E-123<br>E-123<br>E-123 |
| STA. 295+68.00, LT. | | | | | | | | | | | | | | | | | 11' | | | | | | | | | | | | | | | | | | |
| STA. 296+84.00, RT. | SPEED LIMIT | 1 | 24 | 30 | 5.00 | | | | | | 1 | | | | | | 15' | | | | | | | | | | | | | | | | R2-1 | SHS | |
| STA. 296+84.00, LT. | JCT<br>VERMONT | 1<br>1 | 21<br>24 | 15<br>24 | 2.19<br>4.00 | | | | + | | | | | | | | 16'<br>X | | | | | | | | | | | | | | | | M2-1<br>MI-5 | | E-136B<br>E-136B |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | SHS = STANDARD HIGHWAY SIGN BOOK | | |
| | | | | | | | | | | | | FT | FT | FT | FT | FT<br>42 | FT | | EA | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| **TOTALS** | | | | | SF<br>77.6 | SF | EA.<br>1 | SF | | | | FT | | | FT<br>42 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: SUDBURY-MIDDLEBURY
PROJECT NUMBER: STPG SIGN (16)

FILE NAME: stpg sign16 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 8

PLOT DATE: 22-JUL-2014 16:50
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 31 OF 45