QUANTITIES

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ALT A	ALT B	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		6,750		6,750	LF	SHOULDER BERM REMOVAL	203.40	EST.
		1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
		500		500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	16
		1,150		1,150	TON	AGGREGATE SHOULDERS	402.12	-
		60		60	CWT	EMULSIFIED ASPHALT	404.65	-
		1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
		10,000		10,000	LB	BITUMINOUS CRACK SEALING, 'BLOW AND GO' METHOD	417.20	EST.
		300		300	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
		1,500		1,500	HR	FLAGGERS	630.15	EST.
			1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
		1		1	LS	TRAFFIC CONTROL	641.10	-
		144,950		144,950	LF	4 INCH WHITE LINE	646.20	-
		144,950		144,950	LF	4 INCH YELLOW LINE	646.21	-
		12		12	EA	LETTER OR SYMBOL	646.30	EST.
		60		60	LF	CROSSWALK MARKING	646.31	EST.
		1,850		1,850	EA	LINE STRIPING TARGETS	646.76	EST.
		1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
		1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-
		500		500	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	-
		15		15	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.
						BEGIN ALTERNATE A		
121,000				121,000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	247
						END ALTERNATE A		
						BEGIN ALTERNATE B		
	1			1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	7,100			7,100	TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR LATEX)	900.680	55
	820			820	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT (RS-1H OR CRS-1H)	900.683	18
						END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BIT. PAVEMENT
167	SY	BEGIN PROJECT
167	SY	END PROJECT
150	SY	DRIVES AND TOWN HIGHWAYS
16	SY	ROUNDING
500	SY	TOTAL
		ALTERNATE A
		SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)
120,753	SY	MAINLINE
247	SY	ROUNDING
121,000	SY	TOTAL
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR LATEX)
7,045	TON	MAINLINE
55	TON	ROUNDING
7,100	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: NORTON - CANAAN
PROJECT NUMBER: STP SURF(13)

FILE NAME: p08cl56.dgn
PROJECT LEADER: DOMEY
DESIGNED BY: LOCKE
p08cl56qs.1

PLOT DATE: 07-APR-2010
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 4 OF 11