COMPOSITE QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

STP 2627(I)			STP 2803(I)			SUMMARY OF ESTIMATED QUANTITIES				
BRIDGE	FULL C.E.	ROADWAY	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		33,000			66,000	99,000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	
		200			20	220	LF	DURABLE 8 INCH WHITE LINE, THERMOPLASTIC	646.442	
		150			70	220	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	
		79			24	103	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	
		300				300	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	
		32,500			70,000	102,500	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	
		33,000			66,000	99,000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	
		150			70	220	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	
		79			24	103	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	
		300				300	EA	TEMPORARY CROSSWALK MARKING, PAINT	646.702	
		7200			7800	15,000	EA	LINE STRIPING TARGETS	646.76	
		2600			7500	10,100	SY	GEOTEXTILE UNDER STONE FILL	649.31	
		75			115	190	LB	SEED	651.15	
		380			400	780	LB	FERTILIZER	651.18	
		2			1	3	TON	AGRICULTURAL LIMESTONE	651.20	
		165			50	215	CY	TOPSOIL	651.35	
		760			4000	4760	SY	TEMPORARY EROSION MATTING	653.20	
		455			656	1111	SF	TRAFFIC SIGNS, TYPE A	675.20	
		225				225	LB	TUBULAR STEEL SIGN POST	675.33	
		1225			2125	3350	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	
		2				2	EA	FOUNDATION FOR TUBULAR STEEL SIGN POST	675.43	
		134			169	303	EA	REMOVING SIGNS	675.50	
		29			19	48	EA	ERECTING SALVAGED SIGNS	675.60	
		7			23	30	EA	DELINEATOR WITH STEEL POST	676.10	
		1			1	2	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	
					1	1	CY	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608	
		2			23	25	EA	SPECIAL PROVISION (MANUFACTURED TERMINAL SECTION, FLARED/WEATHERING)	900.620	
					1	1	EA	SPECIAL PROVISION (MANUFACTURED TERMINAL SECTION, TANGENT/WEATHERING)	900.620	
		100			**900**	**1000**	**LF**	**•• SPECIAL PROVISION (BOX BEAM GUARDRAIL REPAIRS, WEATHERING) (NEW MATERIAL)**	**900.640**	
		100			**900**	**1000**	**LF**	**•• SPECIAL PROVISION (BOX BEAM GUARDRAIL REPAIRS, WEATHERING) (SALVAGED MATERIAL)**	**900.640**	
					75	75	LF	SPECIAL PROVISION (HD STEEL BEAM GUARDRAIL, WEATHERING/NESTED)	900.640	
					50	50	LF	SPECIAL PROVISION (HD STEEL BEAM GUARDRAIL, WEATHERING/NESTED W/8 FEET POSTS)	900.640	
		2200			4550	6750	LF	SPECIAL PROVISION (STEEL BEAM GUARDRAIL, WEATHERING)	900.640	
		800				800	LF	SPECIAL PROVISION (STEEL BEAM GUARDRAIL, WEATHERING W/8 FEET POSTS)	900.640	
		850			700	1550	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL DRIVES)	900.675	
		23,500			101,000	124,500	SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	
		325			1350	1675	TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	
		300			1275	1575	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

•• REVISED 02-16-10 BY SEH
ADDED ITEM 900.640 SPECIAL PROVISION (BOX BEAM GUARDRAIL REPAIRS, WEATHERING) (NEW MATERIAL) AND ITEM 900.640 SPECIAL PROVISION (BOX BEAM GUARDRAIL REPAIRS, WEATHERING) (SALVAGED MATERIAL). REMOVED ITEM 900.640 SPECIAL PROVISION (BOX BEAM GUARDRAIL REPAIRS, WEATHERING).

COMPOSITE QUANTITY SHEET #3

PROJECT NAME: MIDDLEBURY & RIPTON - HANCOCK

PROJECT NUMBER: STP 2627(I) & STP 2803(I)

FILE NAME: p08c160.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p08c160quan3.i

PLOT DATE: 18-SEP-2013 17:08
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 5 OF 114