QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY(NO STATE/FEDERAL PARTICIPATION)	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			125	125	HR	TRUCK RENTAL	608.37	EST.
			200	200	HR	LOADER RENTAL, TYPE I	608.40	EST.
			5	5	TON	DUST AND ICE CONTROL WITH CALCIUM	609.15	EST.
			200	200	CY	STONE FILL, TYPE I	613.10	6
			400	400	CY	STONE FILL, TYPE II	613.11	23
			45	45	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	0.2
			100	100	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11	2.8
			170	170	SF	DETECTABLE WARNING SURFACE	618.30	-
			40	40	EA	YIELDING MARKER POSTS	619.17	EST.
			1400	1400	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	20.5
			100	100	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	EST.
			175	175	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	2.4
			5	5	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
			5	5	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
			1000	**1000**	**LF**	**•• ADJUST HEIGHT OF GUARDRAIL**	**621.79**	**EST.**
			4700	4700	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	54
8				8	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
			1700	1700	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			2500	2500	HR	FLAGGERS	630.15	EST.
		0.5		0.5	LS	FIELD OFFICE, ENGINEERS	631.10	-
		0.5		0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
		0.5		0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		0.5		0.5	LU	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.25	-
			0.5	0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1	1	LS	TRAFFIC CONTROL (STP 2627(1))	641.10	-
			4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			32,500	32,500	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	535
			33,000	33,000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	815
			200	200	LF	DURABLE 8 INCH WHITE LINE, THERMOPLASTIC	646.442	49
			150	150	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	12
			79	79	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
			300	300	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	23
			32,500	32,500	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
			33,000	33,000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
			150	150	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
			79	79	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
			300	300	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

•• REVISED 02-16-10 BY SEH
ADDED ITEM 621.79, ADJUST HEIGHT OF GUARDRAIL

QUANTITY SHEET #2

PROJECT NAME: MIDDLEBURY

PROJECT NUMBER: STP 2627(1)

FILE NAME: p06c222.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06c222quan2.i

PLOT DATE: 18-SEP-2013 17:08
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 16 OF 114