

# TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS		NEW & SALVAGED SIGNS				EXIST POST	NO. OF POSTS	NEW SIGN POSTS														REMARKS	SIGN DETAIL			
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN			SALV TIS	FLANGED CHANNEL			SQUARE STEEL (in)			TUBULAR ALUMINUM (in)			TUBULAR STEEL (in)					W-SHAPE STEEL		DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											1.2	2.0	3.0	1.75	2.0	2.5	3.0	4.0	4.0	4.0	MOD	3.0	3.5		4.0	5.0		

SHS = FHWA STANDARD SIGNS BOOK

MIDDLEBURY: 62+29.0, LT		1	21	15	2.19					1					16.0	X	X												SIGN ID CODE M2-1		SHS
		1	24	24	4.00																							SIGN ID CODE MI-4		SHS	
64+72.0, LT		1	36	36	9.00					2					14.33	X	X											SIGN ID CODE W3-1		SHS	
68+09.0, RT		1	30	18	3.75					1					12.42	X	X											SIGN ID CODE VD-18		E-128B	
71+94.0, RT		1	36	36	9.00					2					11.67	X	X											SIGN ID CODE W3-1		SHS	
77+15.0, RT		1	24	30	5.00					1					14.33	X	X											SIGN ID CODE VR-017		E-141	
77+53.0, RT										1					13.50	X	X											SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-	
		1	30	30	6.25																							BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		SHS E-138	
83+14.0, RT										1					14.33	X	X											SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-	
		1	30	30	6.25																							BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		SHS E-138	
		1	18	6	0.75																							SIGN ID CODE RI-4		SHS	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

<b>TOTALS</b>	SF 47.03	SF	EA. 3	SF		LF	LF	LF	LF	EA.	LB	LB	LB	EA.	LB	EA.	EA.	LB
---------------	----------	----	-------	----	--	----	----	----	----	-----	----	----	----	-----	----	-----	-----	----

**TRAFFIC SIGN SUMMARY SHEET #2**

PROJECT NAME: MIDDLEBURY  
PROJECT NUMBER: STP 2627(1)

FILE NAME: p06c222.dgn  
PROJECT LEADER: D.E.G.  
DESIGNED BY: M.J.L.  
IPARM FILE: p06c222+ss02.i

PLOT DATE: 18-SEP-2013 17:09  
DRAWN BY: C.A.K.  
CHECKED BY: D.W.E.  
SHEET 37 OF 114