STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS (SHS = FHWA STANDARD SIGNS BOOK)	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
RIPTON: 211+12.0, LT	STEAM MILL RD						1				1					X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 1250 0116 0400	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		SHS E-138
211+71.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															SIGN ID CODE VR-017		E-141
212+06.0, LT		1	48	24	8.00						2					X		X															SIGN ID CODE WI-6R		SHS
214+50.0, LT		1	30	30	6.25						1					X		X															SIGN ID CODE WI-10L		SHS
	35 M.P.H.	1	18	18	2.25																												SIGN ID CODE WI3-1		SHS
216+69.0, RT		1	30	30	6.25						1					X		X															SIGN ID CODE WI1-2 SIGN SHALL BE FLUORESCENT YELLOW GREEN.		SHS
	NEXT 2500 FT	1	24	18	3.00																												SIGN ID CODE WI6-4 SIGN SHALL BE FLUORESCENT YELLOW GREEN.		SHS
219+22.0, RT	EAST	1	24	12	2.00						1					X		X															SIGN ID CODE M3-2		E-136B
	SCENIC	1	30	15	3.13																												SIGN ID CODE VM-064	113	
	VERMONT 125	1	30	24	5.00																												SIGN ID CODE MI-4		E-136B
	1250 0116 0416	1	6	10	0.42																												SIGN ID CODE VD-700		E-138
												LF	LF	LF	LF	LF 98	LF		EA.	LB	LB	LB		LB	LB	LB	LB							
TOTALS		SF 47.97	SF	EA. 1	SF							LF			LF 98					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #13

PROJECT NAME: RIPTON - HANCOCK

PROJECT NUMBER: STP 2803(I)

FILE NAME: p08cl60.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p08cl60tssl3.i

PLOT DATE: 18-SEP-2013 17:11
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 109 OF 114