

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1		1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
									110		110		CY	COMMON EXCAVATION	203.15				
									75		75		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
									1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									130		130		CY	STRUCTURE EXCAVATION	204.25				
									80		80		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
									7		7		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
									1145		1145		LB	REINFORCING STEEL	507.15				
									1		1		GAL	WATER REPELLENT, SILANE	514.10				
									7		7		CY	REMOVAL OF CONCRETE OR MASONRY	529.25				
									5		5		CY	CONCRETE, CLASS D	541.31				
			16								16		HR	POWER BROOM RENTAL, TYPE II	608.31				
									150		150		CY	STONE FILL, TYPE II	613.11				
									75		75		CY	STONE FILL, TYPE III	613.12				
									80		80		HR	FLAGGERS	630.15				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1		1		LS	MOBILIZATION/DEMobilIZATION	635.11				
			1								1		LS	TRAFFIC CONTROL	641.10				
									300		300		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							120				120		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							30				30		LB	SEED	651.15				
							250				250		LB	FERTILIZER	651.18				
							1				1		TON	AGRICULTURAL LIMESTONE	651.20				
							1				1		TON	HAY MULCH	651.25				
							70				70		CY	TOPSOIL	651.35				
							225				225		SY	GRUBBING MATERIAL	651.40				
							1				1		LS	EPSC PLAN	652.10				
							80				80		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							300				300		SY	TEMPORARY EROSION MATTING	653.20				
							1200				1200		SY	PERMANENT EROSION MATTING	653.21				
							6				6		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
							40				40		CY	VEHICLE TRACKING PAD	653.35				
							1				1		EACH	FILTER BAG	653.45				
							675				675		LF	PROJECT DEMARCATION FENCE	653.55				
									5		5		CY	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608				
									20		20		CY	SPECIAL PROVISION (GABION RETAINING WALL)	900.608				
									192		192		LF	SPECIAL PROVISION (ALUMINUM PIPE LINER)(60")EXISTING 72" PIPE)	900.640				
									80		80		LF	SPECIAL PROVISION (TEST BORINGS)	900.640				
									1		1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)	900.645				
									1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645				

PROJECT NAME: IRASBURG  
 PROJECT NUMBER: STP CULV(20)  
 FILE NAME: ...drawing\z08cl94qty.dgn PLOT DATE: 10/28/2010  
 PROJECT LEADER: G. BOGUE DRAWN BY: J. SOTER  
 DESIGNED BY: M. CHENETTE CHECKED BY: T. KNIGHT  
**QUANTITY SHEET** SHEET 5 OF 15

