

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
								220			220		CY	COMMON EXCAVATION	203.15				
								150			150		CY	GRANULAR BORROW	203.32				
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								156			156		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
								100			100		CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26				
								1			1		CWT	EMULSIFIED ASPHALT	404.65				
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								1			1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
								3			3		CY	CONCRETE, CLASS D	541.31				
								15			15		CY	STONE FILL, TYPE I	613.10				
								50			50		LF	REMOVING AND RESETTING FENCE	620.50				
								150			150		LF	REMOVE AND RESET GUARDRAIL	621.75				
								5			5		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76				
								3			3		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77				
								40			40		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								300			300		HR	FLAGGERS	630.15				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
								1			1		LS	MOBILIZATION/DEMobilIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL	641.10				
								2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
								232			232		LF	4 INCH WHITE LINE	646.20				
								232			232		LF	4 INCH YELLOW LINE	646.21				
								60			60		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								40			40		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								4			4		LB	SEED	651.15				
								35			35		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								28			28		CY	TOPSOIL	651.35				
								330			330		SY	TEMPORARY EROSION MATTING	653.20				
								5			5		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								285			285		LF	BARRIER FENCE	653.50				
								4			4		EACH	REMOVING SIGNS	675.50				
								2			2		EACH	ERECTING SALVAGED SIGNS	675.60				
								1			1		EACH	SETTING SALVAGED POSTS	675.61				
								33			33		CY	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608				
								1			1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
								1			1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				

PROJECT NAME: BRIDPORT  
PROJECT NUMBER: STP CULV(2I)

FILE NAME: ...06-quantity sheet1.dgn  
PROJECT LEADER: G. BOGUE  
DESIGNED BY: M. CHENETTE  
**QUANTITY SHEET 1**

PLOT DATE: 11/5/2010  
DRAWN BY: M. CHENETTE  
CHECKED BY: E. ALLING  
SHEET 4 OF 14

