

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES					TOTALS	DESCRIPTIONS			
ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	
225				225	CY	EARTH BORROW	203.30	-	
1				1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	
51000				51000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	122	
1080				1080	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	9	
48500				48500	SY	RECLAIMED STABILIZED BASE	310.20	240	
1850				1850	TON	AGGREGATE SHOULDERS	402.12	9	
415				415	CWT	EMULSIFIED ASPHALT	404.65	4	
1				1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	
23000				23000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	163	
1				1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	
1				1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-	
1				1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-	
1				1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-	
		135		135	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	3	
		100		100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.	
40				40	LF	15" CPEP	601.0910	EST.	
1				1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.	
300				300	HR	POWER GRADER RENTAL	608.15	EST.	
300				300	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.	
100				100	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.	
160				160	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.	
160				160	HR	TRUCK RENTAL	608.37	EST.	
160				160	HR	LOADER RENTAL, TYPE I	608.40	EST.	
	1520			1520	CY	STONE FILL, TYPE I	613.10	13.9	
	50			50	CY	STONE FILL, TYPE II	613.11	EST.	
220				220	LF	TREATED TIMBER CURB	616.35	7	
2				2	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	0.4	
40				40	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-	
3				3	EA	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12	-	
66				66	EA	YIELDING MARKER POSTS	619.17	2	
2800				2800	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	7.5	
300				300	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	12.5	
50				50	LF	STEEL BEAM GUARDRAIL, GALVANIZED / NESTED W/8 FEET POSTS	621.207	-	
150				150	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	2.5	
9				9	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-	
17				17	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-	
4				4	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	-	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
49424	SY	MAINLINE
534	SY	BRIDGES
920	SY	SIDEROADS
122	SY	ROUNDING
51000	SY	TOTAL
		RECLAIMED STABILIZED BASE
38841	SY	WESTFORD MAINLINE
8671	SY	FAIRFAX MAINLINE
748	SY	SIDEROADS
240	SY	ROUNDING
48500	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
12665	TON	MAINLINE WEARING COURSE (TYPE IVS)
210	TON	SIDEROAD WEARING COURSE (TYPE IVS)
40	TON	BRIDGE WEARING COURSE (TYPE IVS)
8314	TON	MAINLINE BASE COURSE (TYPE IIS)
130	TON	SIDEROAD BASE COURSE (TYPE IIS)
1478	TON	LEVELING (TYPE IVS)
163	TON	ROUNDING
23000	TON	TOTAL
		STONE FILL, TYPE I
1482	CY	DITCH CLEANING
24.1	CY	SLOPE EROSION REPAIR
13.9	CY	ROUNDING
1520	CY	TOTAL

PROJECT NAME: WESTFORD - FAIRFAX	PLOT DATE: 31-OCT-2012 13:56
PROJECT NUMBER: STP 2804(1)	DRAWN BY: STANTEC
FILE NAME: p08c212.dgn	CHECKED BY: JLL
DESIGNED BY: STANTEC	SHEET 6 OF 79
IPARM FILE: p08c212qs01.i	