

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES					TOTALS	DESCRIPTIONS			
	ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND
	2665				2665	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
	1520				1520	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
	4560				4560	HR	FLAGGERS	630.15	EST.
				1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
				1	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
				1	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
	1				1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
	1				1	LS	TRAFFIC CONTROL	641.10	-
	1				1	LS	PUBLIC RELATIONS OFFICER	641.12	-
	2				2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
	63400				63400	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	146
	54200				54200	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	85
	250				250	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	3
	53				53	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
	126700				126700	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	192
	108400				108400	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	170
	500				500	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	6
	106				106	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
	3000				3000	EA	LINE STRIPING TARGETS	646.76	28
		7600			7600	SY	GEOTEXTILE UNDER STONE FILL	649.31	47
		250			250	SY	GEOTEXTILE FOR SILT FENCE	649.51	EST.
		40			40	LB	SEED	651.15	EST.
		250			250	LB	FERTILIZER	651.18	EST.
		1			1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
		1			1	TON	HAY MULCH	651.25	EST.
		25			25	CY	TOPSOIL	651.35	EST.
		850			850	SY	TEMPORARY EROSION MATTING	653.20	50
	315				315	SF	TRAFFIC SIGNS, TYPE A	675.20	3.31
	1190				1190	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	10
	103				103	EA	REMOVING SIGNS	675.50	-
	18				18	EA	ERECTING SALVAGED SIGNS	675.60	-
	24				24	EA	DELINEATOR WITH STEEL POST	676.10	-
	16				16	EA	REMOVAL OF EXISTING DELINEATOR	676.12	-
	1				1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
	1780				1780	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	22
	5650				5650	TON	SPECIAL PROVISION (SUBBASE, RAP FOR RECLAIMING)	900.680	8

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		GEOTEXTILE UNDER STONE FILL
6672	SY	DITCH CLEANING
881	SY	SLOPE EROSION REPAIR
47	SY	ROUNDING
7600	SY	TOTAL
		TEMPORARY EROSION MATTING
375	SY	DITCH CLEANING
225	SY	M.T.S. CONSTRUCTION
200	SY	SEED PROTECTION (EST.)
50	SY	ROUNDING
850	SY	TOTAL

PROJECT NAME: WESTFORD - FAIRFAX  
PROJECT NUMBER: STP 2804(1)

FILE NAME: p08c212.dgn  
PROJECT LEADER: JLL  
DESIGNED BY: STANTEC  
IPARM FILE: p08c212qs02.i

PLOT DATE: 31-OCT-2012 13:56  
DRAWN BY: STANTEC  
CHECKED BY: JLL  
SHEET 7 OF 79