

ITEM DETAIL SUMMARY SHEET 5

LOCATION			GUARDRAIL							MISCELLANEOUS											REMARKS	
BEGIN MILE STA.	END MILE STA.	POS.	621.20	621.205	621.207	621.21	621.50	621.60	621.70	621.80	203.30	402.12	601.0910	604.412	613.10	613.11	616.35	616.47	617.10	617.12		619.17
			S.B. G.R. GALV. LF	S.B. G.R. GALV. 8' POST LF	S.B. G.R. GALV./NEST. W/8' POSTS LF	H.D. S.B. G.R. GALV. LF	MTS, FLARED EA	ANCHOR FOR S.B. RAIL EA	G.R. APP. SECTION GALV. TYPE I EA	REMOVAL & DISPOSAL OF GUARDRAIL LF	EARTH BORROW CY	AGG. SHLDRS. TON	15" CPEP LF	REHAB DI, CB, OR MH, CLASS I EA	STONE FILL, TYPE I CY	STONE FILL, TYPE II CY	TREATED TIMBER CURB LF	BIT. CONC. GUT. & TRAFF. ISL. TON	RELOC. MAILBOX, SNGL. SUPP. EACH	RELOC. MAILBOX, MULT. SUPP. EACH		YIELDING MARKER POSTS EACH
VT ROUTE 128 FAIRFAX (CONT.)																						
7+46	10+96.5	RT	100				2		2	267	50											INSTALL M.T.S., FLARED @ 7+48.5, RT AND 10+59, RT; SEE BRIDGE DETAIL SHEET NO. 3
21+56		LT																		1		
25+37		LT																	1			
SHEET 1 SUBTOTALS:			1982.5	50	-	147.5	4	12	-	1461	100	1963	20	1	23	50	89	1.1	15	-	64	
SHEET 3 SUBTOTALS:			710	237.5	50	-	3	5	2	937	75	-	20	-	1.1	-	124	0.5	24	2	-	* THESE TOTALS ARE CARRIED FORWARD TO THE DETAILED SUMMARY OF QUANTITIES ON THE QUANTITY SHEETS
SHEET 5 SUBTOTALS:			100	-	-	-	2	-	2	267	50	-	-	-	-	-	-	-	1	1	-	
PROJECT SUBTOTALS:			2792.5	287.5	50	147.5	9	17	4	2665	225	1963	40	1	24.1	50	213	1.6	40	3	64	
ROUNDINGS:			7.5	12.5	-	2.5	-	-	-	-	-	17	-	-	-	-	7	0.4	-	-	-	2
TOTALS:			2800	300	50	150	9	17	4	2665	225	1980	40	1	24.1*	50	220	2	40	3	66	

**ITEM
DETAIL
SUMMARY
SHEET #5**

PROJECT NAME: WESTFORD - FAIRFAX	PLOT DATE: 31-OCT-2012 13:56
PROJECT NUMBER: STP 2804(1)	DRAWN BY: STANTEC
FILE NAME: p08c212.dgn	CHECKED BY: JLL
DESIGNED BY: STANTEC	SHEET 12 OF 79
IPARM FILE: p08c212ids05.i	