



SUPERELEVATION BANKING NOTES:

1. THE CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING AND MAINTAINING THE HORIZONTAL AND VERTICAL GEOMETRY OF THE EXISTING ROADWAY.
2. THE MAXIMUM ROLL-OVER BETWEEN LANE AND SHOULDER CROSS SLOPES ON THE OUTSIDE (HIGH SIDE) OF A SUPERELEVATED CURVE SHALL BE SEVEN PERCENT. SHOULDER CROSS SLOPE ON THE INSIDE (LOW SIDE) OF A SUPERELEVATED CURVE SHALL BE A MINIMUM OF SIX PERCENT AND MATCH THE ADJACENT LANE CROSS SLOPE WHEN THE LANE CROSS SLOPE EXCEEDS SIX PERCENT.
3. SUPERELEVATION RATES AND RUNOFF LENGTHS WERE DETERMINED USING A DESIGN SPEED EQUAL TO THE POSTED SPEED. A MAXIMUM SUPERELEVATION RATE OF 0.08 IS USED IN AREAS WITH A POSTED SPEED ABOVE 30 MPH. IN THE 30 MPH ZONE A MAXIMUM SUPERELEVATION RATE OF 0.04 WAS USED. IN AREAS WITH AN INTERSECTING SIDE ROAD A MAXIMUM SUPERELEVATION RATE OF 0.06 WAS USED. SEE VAOT STANDARD B-1 FOR MORE INFORMATION.



NOT TO SCALE
SUPERELEVATION BANKING DIAGRAMS SHEET #2

PROJECT NAME:	WESTFORD - FAIRFAX	PLOT DATE:	31-OCT-2012 13:58
PROJECT NUMBER:	STP 2804(1)	DRAWN BY:	STANTEC
FILE NAME:	p08c212.dgn	CHECKED BY:	JLL
PROJECT LEADER:	JLL	SHEET	53 OF 79
DESIGNED BY:	STANTEC		
IPARM FILE:	p08c212sbd2.i		