STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 06

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS | | | NEW & SALVAGED SIGNS | | | | EXIST POST | | NEW SIGN POSTS | | | | | | | | | | | | | | | | | | | | | | | REMARKS | SIGN DETAIL | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | EA | WIDTH (in) | HEIGHT (in) | "A" | "B" | SALV SIGN | SALV TIS | RETAIN | SALVAGE | NO. OF POSTS | FLANGED CHANNEL lb/ft | | | SQUARE STEEL (in) lb/ft | | | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft | | | FOUNDATION | TUBULAR STEEL Ø (in) lb/ft | | | | W-SHAPE STEEL FTG. SIZE | | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | | DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
| | | | | | | | | | | | | | | | 1.75 | 2.0 | 2.5 | | | 3.0 | 4.0 | 4.0 MOD | | 3.0 | 3.5 | 4.0 | 5.0 | 24" | 30" | | | | | | |
| | | | | | | | | | | | | 1.12 | 2.0 | 3.0 | 1.88 | 2.42 | 3.35 | | | 1.3 | 1.7 | 1.7 | | 7.6 | 9.0 | 10.8 | 14.6 | | | | | | | | |
| **WESTFORD (CONT.)** | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 296+08, RT | 1280 0416 0560 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | 8 / X 15.04 | 8 | | X | | | | | | | | | | | | | | | | E-138 | |
| 303+24, RT | ⟷ | | | | | | 1 | | | | 2 | | | | | 14x2 X 67.76 | | X | | | | | | | | | | | | | | | MOUNT SALVAGED SIGN ON NEW POSTS | - | - |
| 305+15, LT | 1280 0416 0580 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | 8 / X 15.04 | 8 | | X | | | | | | | | | | | | | | | | E-138 | |
| 328+00, LT | 1280 0416 0620 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | 8 / X 15.04 | 8 | | X | | | | | | | | | | | | | | | | E-138 | |
| 338+63, RT | 1280 0416 0640 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | 8 / X 15.04 | 8 | | X | | | | | | | | | | | | | | | | E-138 | |
| **FAIRFAX** 8+55, LT | BROWN'S RIVER | | | | | | 1 | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | MOUNT SALVAGED SIGN ON NEW POST | - | - |
| 11+02, LT | 1280 0604 0020 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | 8 / X 15.04 | 8 | | X | | | | | | | | | | | | | | | | E-138 | |
| 21+35, RT | JCT VERMONT 104 END VERMONT 128 1280 0604 0040 | | | | | | 1<br>1<br>1<br>1<br>1 | | | | 2 | | | | | 16<br>18<br>X<br>82.25 | | X | | | | | | | | | | | | | | | | MOUNT SALVAGED SIGNS ON NEW POSTS | -<br>-<br>-<br>-<br>- | -<br>-<br>-<br>-<br>- |
| 28+03, LT | STOP 1280 0604 0053 B-B | 1<br>1 | 30<br>6 | 30<br>10 | 6.25<br>0.42 | | | | | | 1 | | | | | 12<br>X<br>29.04 | | X | | | | | | | | | | | | | | | | SIGN ID CODE R1-1<br>MOUNT MILE MARKER PLAQUE BACK-TO-BACK AND BELOW STOP SIGN | | SEE FHWA SHS<br>E-138 |
| 28+44, LT | McNALL RD STOP | 1 | 30 | 30 | 6.25 | | 1 | | | | 1 | | | | | 14<br>X<br>33.88 | | X | | | | | | | | | | | | | | | | MOUNT SALVAGED STREET SIGN 90 DEGREES TO AND 6" ABOVE NEW STOP SIGN<br>SIGN ID CODE R1-1 | - | -<br>SEE FHWA SHS |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | 75.20 | 212.96 | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | FT | FT | FT | FT 40 | FT 88 ~~105~~ | FT | | EA | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| **TOTALS** | | | SF 15.02 | | SF | EA. 8 | | SF | | | | FT | | | | | FT 128 145 | | | LB | | | EA. | LB | | | | EA. | EA. | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: WESTFORD - FAIRFAX
PROJECT NUMBER: STP 2804(1)

FILE NAME: p08c212.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
**IPARM FILE: p08c212tss06.i**
PLOT DATE: 31-OCT-2012 13:5
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 67 OF 79