

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
								BRIDGE 7	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								340		340		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
								1		1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								1		1		EACH	SHORING SUPERSTRUCTURE BEARINGS (ABUTMENT)	502.11				
								1		1		EACH	SHORING SUPERSTRUCTURE BEARINGS (PIER)	502.11				
								6450		6450		LB	REINFORCING STEEL	507.15				
								30		30		LF	DRILLING AND GROUTING DOWELS	507.16				
								73		73		EACH	MECHANICAL BAR CONNECTOR	507.19				
								100		100		GAL	WATER REPELLENT, SILANE	514.10				
								40		40		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
								75		75		LF	BRIDGE EXPANSION JOINT, VERMONT	516.11				
													BEGIN OPTION AA					
								60		60		LF	JOINT SEALER, HOT Poured	524.11				
								60		60		LF	JOINT SEALER, COLD Poured	524.13				
													END OPTION AA					
								1220		1220		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
								1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
								1000		1000		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
								3		3		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
								111		111		SY	REPOINTING MASONRY	602.30				
								32		32		HR	POWER GRADER RENTAL	608.15				
								450		450		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
								80		80		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								150		150		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
								1		1		LS	MOBILIZATION/DEMobilIZATION	635.11				
								1		1		LS	TRAFFIC CONTROL	641.10				
								1		1		LS	PUBLIC RELATIONS OFFICER	641.12				
								180		180		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17				
								930		930		LF	DURABLE 4 INCH WHITE LINE	646.400				
								930		930		LF	DURABLE 4 INCH YELLOW LINE	646.410				
								26		26		LF	DURABLE 24 INCH STOP BAR	646.480				
								150		150		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
								2		2		EACH	TEMPORARY LETTER OR SYMBOL	646.690				
								55		55		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS AA LOW CEMENT)	900.608				
								32		32		LF	SPECIAL PROVISION (BRIDGE FIBERGLASS DRAIN SYSTEM)	900.640				
								1		1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE) (N.A.B.I.)	900.650				
								1		1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				