



BILL OF MATERIALS				
QTY	MARK	SHAPE	LENGTH	REMARKS
1	1J1	VERMONT JOINT ASSEMBLY		
1	1a1	L 8" x 4" x 1/2"	34'-9 1/2"	
1	1a2	L 8" x 4" x 1/2"	34'-9 1/2"	
34	S1	3/4" x 10" Welded Stud		Str
34	S2	3/4" x 10" Welded Stud		Beut
2	1r1	1/16" x 3" Butyl Rubber x 35'		
10	3S1	GIRDER SUPPORT PLATES		
1	4T1	TROUGH		
1	5P1	JOINT PLATE		
1	5P2	JOINT PLATE		
1	5P3	JOINT PLATE		
1	5P4	JOINT PLATE		
10	1a7	L 8" x 4" x 1/2"	1'-4 1/4"	
20		Bolt 3/4" x 3 1/2" Lg		
10		Bolt 3/4" x 1 1/2" Lg w/ Nut		

STRUCTURES
COPY

RECEIVED
OK'D BY: HES OK'D BY: DDB
JUN 10 2009
RESUBMIT APPROVED AS NOTED
BY: CPW DATE: 6/10/09

REV NO.	DATE	DESCRIPTION
1	6-9-2009	REVISED PER APPROVAL COMMENTS
0	6-3-2009	SUBMITTED FOR APPROVAL

HOLES AS NOTED
MATERIAL: AASHTO M 270 GRADE 36 GALV

DRAWING COVERS

VERMONT JOINT LAYOUT (ABUTMENT)

PROJECT	MORETOWN STP DECK (37)
LOCATION	VERMONT 100B BRIDGE NO. 7
ENGINEER	VERMONT AGENCY OF TRANSPORTATION
CUSTOMER	CSS CONSTRUCTION

MERRIMACK SHEET METAL

119 HALL STREET
CONCORD NH 03301

Tel. 603.224.7766
Fax 603.224.7925

DRAWN BY: RL
CHECKED BY: JD
JOB NO: #2808
DWG: F1