

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	BRIDGE (US 2 Br. 48)	BRIDGE (VT 100B Br. 4)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								450	580		1030		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
								4	3		7		CWT	EMULSIFIED ASPHALT	404.65				
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								70	60		130		GAL	WATER REPELLENT, SILANE	514.10				
								100	50		150		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
								1280	635		1915		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
														BEGIN OPTION AA					
								170	105		275		LF	JOINT SEALER, HOT POURED	524.11				
								170	105		275		LF	JOINT SEALER, COLD POURED	524.13				
														END OPTION AA					
								1605	895		2500		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
								11525	5680		17205		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
								40	8		48		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								800	600		1400		HR	FLAGGERS	630.15				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
							1				1		LS	MOBILIZATION/DEMOLITION	635.11				
								1			1		LS	TRAFFIC CONTROL (US 2 - BRIDGE NO. 48)	641.10				
									1		1		LS	TRAFFIC CONTROL (VT 100B - BRIDGE NO. 4)	641.10				
								750	630		1380		LF	DURABLE 4 INCH WHITE LINE	646.400				
								645	610		1255		LF	DURABLE 4 INCH YELLOW LINE	646.410				
								11			11		LF	DURABLE 24 INCH STOP BAR	646.480				
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
								1	1		2		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
								1	1		2		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650				
								323	222		545		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				