QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			13	13	SF	DETECTABLE WARNING SURFACE	618.30	0.5
			65	65	LF	REMOVING AND RESETTING FENCE	620.50	-
			90	90	LF	REMOVAL OF EXISTING FENCE	620.55	-
			91.5	91.5	LF	STEEL BEAM GUARDRAIL, GALVANIZED (COATED BLACK)	621.20	-
			3	3	EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-
			2	2	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-
			2	2	EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 4 RAIL BOX BEAM (COATED BLACK)	621.73	-
			60	60	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	0.4
			200	200	LF	TEMPORARY TRAFFIC BARRIER	621.90	10
			400	400	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			800	800	HR	FLAGGERS	630.15	EST.
		1		1	LS	FIELD OFFICE, ENGINEERS	631.10	-
		1		1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
		1		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		3000		3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	EST.
			1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1	1	LS	TRAFFIC CONTROL	641.10	-
			2	2	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			365	365	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	1
			365	365	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	1
			70	70	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	1
			605	605	LF	TEMPORARY 4 INCH WHITE LINE	646.600	3
			405	405	LF	TEMPORARY 4 INCH YELLOW LINE	646.610	2
			10	10	LF	TEMPORARY 24 INCH STOP BAR	646.680	-
			70	70	LF	TEMPORARY CROSSWALK MARKING	646.700	10
			900	900	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	40
			80	80	SY	GEOTEXTILE UNDER STONE FILL	649.31	6
			90	90	SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41	8
45				45	SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	6
50				50	LB	SEED	651.15	EST.
400				400	LB	FERTILIZER	651.18	EST.
1				1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
1				1	TON	HAY MULCH	651.25	EST.
25				25	CY	TOPSOIL	651.35	4
80				80	SY	GRUBBING MATERIAL	651.40	6
1				1	LS	EPSC PLAN	652.10	-
40				40	HR	MONITORING EPSC PLAN	652.20	EST.
1				1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

CHA

QUANTITY SHEET #2

PROJECT NAME: JERICHO
PROJECT NUMBER: STP FTBR (3)

PROJECT LEADER: M.D.S.
DESIGNED BY: C.R.H.
DWG. NO.: QUAN-2

PLOT DATE: 4/7/2014
DRAWN BY: C.R.H.
CHECKED BY: D.E.G.
SHEET 10 OF 62

FILE NAME = V:\Projects\VNY\K2\21113\CADD\MSTN\08F004\Consultants\x08f004quan2.dgn
DATE/TIME = 4/7/2014
USER = KHE