QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
300				300	SY	TEMPORARY EROSION MATTING	653.20	EST.
10				10	SY	PERMANENT EROSION MATTING	653.21	1
12				12	CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	-
2				2	EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-
175				175	LF	BARRIER FENCE	653.50	2
1				1	LS	TREE PROTECTION	656.85	-
			7	7	EACH	REMOVING SIGNS	675.50	-
			1	1	EACH	ERECTING SALVAGED SIGNS	675.60	-
			1	1	EACH	SETTING SALVAGED POSTS	675.61	-
			115	115	LF	WIRED CONDUIT (1¼") (PVC)	678.23	5.6
			2	2	EACH	PULL BOX, STANDARD	678.25	-
			5	5	EACH	LIGHT POLE BASE	679.21	-
			4	4	EACH	REMOVING AND RESETTING LIGHT POLE	679.25	-
			1	1	EACH	SPECIAL PROVISION (ORNAMENTAL STREET LIGHT)	900.620	-
			1	1	EACH	SPECIAL PROVISION (RELOCATE SIGN)	900.620	-
			100	100	LF	SPECIAL PROVISION (ORNAMENTAL FENCE)	900.640	2
			36	36	LF	SPECIAL PROVISION (REMOVAL OF TEMPORARY TRAFFIC BARRIER)	900.640	-
	220			220	LF	SPECIAL PROVISION (ROCK DOWELING)	900.640	-
	1			1	LS	SPECIAL PROVISION (ROCK DOWEL TESTING)	900.645	-
			1	1	LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650	-
			1	1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-
	300			300	SY	SPECIAL PROVISION (THIN POLYMER OVERLAY)	900.675	4
			22	22	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	2
			2	2	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

CHA

QUANTITY SHEET #3

PROJECT NAME: JERICHO
PROJECT NUMBER: STP FTBR (3)

PROJECT LEADER: M.D.S.
DESIGNED BY: C.R.H.
DWG. NO.: QUAN-3

PLOT DATE: 4/7/2014
DRAWN BY: C.R.H.
CHECKED BY: D.E.G.
SHEET 11 OF 62

FILE NAME = V:\Projects\ANY\K2\21113\CADD\MSTN\08F004\Consultants\x08f004quan3.dgn
DATE/TIME = 4/7/2014
USER = KHG