ITEM DETAIL SUMMARY SHEET

LOCATION			UNDERDRAIN				CURB		SIDEWALK		GUARDRAIL				MISCELLANEOUS									REMARKS
			605.10	605.20	605.23	605.95	616.21	616.41	618.10	618.30	621.20	621.60	621.73	621.80	204.20	620.50	620.55	678.23	678.25	679.21	679.25	900.620	900.640	
BEGIN STATION	END STATION	POS.	6 IN. UND. PIPE	6 IN. UND. CAR. PIPE	12 IN. UND. CAR. PIPE	UND. FLSH. BASIN	VERT. GRAN. CRB.	REM. OF EX. CRB.	PCC SW 5 IN	DET. WARN. SURF.	(S.B. GR GALV) (COATED BLK)	ANCHOR FOR S.B. RAIL	(GR APPR. SECT, 4 RL. BX. BM.) (COATED BLK)	R&D OF GR	TRENCH EX. OF EARTH	REM. & RES. FENCE	REM. OF EX. FENCE	WIRED CONDUIT (1/4"PVC)	PULL BOX, STD.	LT. POLE BASE	R&R LT. POLE	S.P. (ORN. ST. LT.)	S.P. (REM. TTB)	
			LF	LF	LF	EACH	LF	LF	SY	SF	LF	EACH	EACH	LF	CY	LF	LF	LF	EACH	EACH	EACH	EACH	LF	
PEDESTRIAN BRIDGE/ SIDEWALK																								
10+17.2	10+30.0	LT/RT					16.0																	SEE VTRANS' STD. C-10, TYPICAL SECTIONS #1, AND PEDESTRIAN BRIDGE/SIDEWALK CROSS SECTION #1 FOR INSTALLATION DETAILS.
10+17.8	10+34.0	RT							10.0	12.5														INSTALL PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, WITH SIDEWALK RAMP TYPE I. INSTALL DETECTABLE WARNING SURFACE AS SHOWN ON VTRANS' STD. SHEET C-3A.
10+26.9	10+31.9	LT															12.0							
11+04.9	11+34.6	LT															30.0							
11+05.6	11+21.7	LT															16.0							
11+06.0	11+82.0	RT							42.3															SEE TYPICAL SECTIONS #2 AND #3 PEDESTRIAN BRIDGE/SIDEWALK AND CROSS SECTION #2 AND #3 FOR CROSS SLOPE AND WIDTH TRANSITION DETAILS.
11+08.4	11+74.0	LT/RT													17.7			42.6	1	2	2			SEE SECTIONS 204, 678, AND 679 OF THE STANDARD SPECIFICATIONS AND VTRANS' STD SHEETS E-173, E-180A AND E-180B FOR CONSTRUCTION DETAILS. EXCAVATION TO DETERMINE EXACT LOCATION OF THE PULL BOX AT STA 11+74 SHALL BE PAID UNDER THE TRENCH EXCAVATION OF EARTH, EXPLORATORY, ITEM 204.22. REMOVE CONDUIT WEST OF THIS LOCATION.
11+24.0	11+73.0	RT					47.7	14.7																SEE PEDESTRIAN BRIDGE/SIDEWALK CROSS SECTIONS #2 AND #3 FOR TOP OF CURB ELEVATIONS. REMOVE EXISTING GRANITE CURBING ADJACENT REMOVED DI. REMOVED GRANITE CURBING TO REMAIN PROPERTY OF THE TOWN.
11+24.0	11+70.3	LT									14.5	1	1	30.3										SEE VTRANS' STD. SHEETS G-1 AND G-1D FOR CONSTRUCTION DETAILS. SEE GUARDRAIL APPROACH SECTION DETAILS 2 AND 3, SHEETS 42 AND 43 FOR GUARDRAIL APPROACH SECTION DETAILS. PLACE ANCHOR AT STA 11+61.0. REMOVE EXISTING GUARDRAIL.
RED MILL DRIVE																								
20+00.0	20+64.6	RT					65.8	40.2																SEE RED MILL DRIVE CROSS SECTION #1 FOR TOP OF CURB ELEVATIONS. REMOVE EXISTING CONCRETE CURBING ALONG RED MILL DRIVE.
20+00.0	21+18.3	RT									77.0	1	1	29.3										SEE VTRANS' STD. SHEETS G-1 AND G-1D FOR CONSTRUCTION DETAILS. SEE GUARDRAIL APPROACH SECTION DETAILS 1-3, SHEETS 41-43 FOR GUARDRAIL APPROACH SECTION DETAILS. PLACE ANCHOR AT STA 21+08. REMOVE EXISTING GUARDRAIL.
20+02.0	20+64.5	RT														65.0	32.0							REMOVE AND RESET FENCE IN THE LOCATIONS SHOWN ON THE LAYOUT PLAN, SHEET 16, OR AS DIRECTED BY THE ENGINEER. REMOVED FENCE, WHICH IS NOT RESET, TO REMAIN PROPERTY OF THE TOWN. THE CONTRACTOR SHALL COORDINATE DELIVERY LOCATION THROUGH THE ENGINEER.
20+37.9	20+59.7	RT																						
20+03.0	20+59.1	RT	56.0	34.2	12.3	2																		SEE LAYOUT PLAN, SHEET 16, AND STONE MASONRY PLAN AND DETAILS, SHEET 33, FOR LAYOUT. SEE VTRANS' STD.SHEETS D-16 AND D-30 FOR CONSTRUCTION DETAILS. EXCAVATION SHALL BE PAID AS SHOWN ON PROJECT TYPICAL SECTIONS #4.
20+07.0	20+77.1	RT													5.5			66.8	1	3	2	1		SEE SECTIONS 204, 678, AND 679 OF THE STANDARD SPECIFICATIONS AND VTRANS' STD SHEETS E-173, E-180A AND E-180B FOR CONSTRUCTION DETAILS. EXCAVATION TO DETERMINE EXACT LOCATION OF THE JUNCTION BOX AT STA 20+77 SHALL BE PAID UNDER THE TRENCH EXCAVATION OF EARTH, EXPLORATORY, ITEM 204.22. REMOVE CONDUIT SOUTH OF THIS LOCATION, INCIDENTAL TO STRUCTURE EXCAVATION (BRIDGE ITEM).
20+15.1	20+43.4	RT																					36.0	SEE LAYOUT PLAN, SHEET 16 FOR LOCATION OF BARRIER TO BE REMOVED. REMOVED BARRIER TO REMAIN PROPERTY OF THE TOWN. THE CONTRACTOR SHALL COORDINATE DELIVERY LOCATION THROUGH THE ENGINEER.
SUBTOTALS:			56.0	34.2	12.3	2	129.5	54.9	52.3	12.5	91.5	2	2	59.6	23.2	65.0	90.0	109.4	2	5	4	1	36.0	
ROUNDING			2.0	1.8	1.7	-	0.5	0.1	2.7	0.5	-	-	-	0.4	-	-	-	5.6	-	-	-	-	-	
TOTALS:			58.0	36.0	14.0	2	130.0	55.0	55.0	13.0	91.5	2	2	60.0	23.2	65.0	90.0	115.0	2	5	4	1	36.0	

CHA

ITEM DETAIL SUMMARY SHEET

PROJECT NAME: JERICHO
PROJECT NUMBER: STP FTBR (3)

PROJECT LEADER: M.D.S.
DESIGNED BY: C.R.H.
DWG. NO.: IDS-1

PLOT DATE: 4/7/2014
DRAWN BY: C.R.H.
CHECKED BY: D.E.G.
SHEET 12 OF 62

FILE NAME = V:\Projects\VHY\K2\21113\CADD\MSTN\08F0204\Consultants\ids08f0204ids.dgn
DATE/TIME = 4/7/2014
USER = mds