DRAINAGE DETAIL SHEET

LOCATION			PIPE				DRAINAGE STRUCTURES						REMARKS
BEGIN STATION	END STATION	POS.	D IN	L FT	CPEP	TRENCH EX. OF EARTH CY	DEPTH DI FT	CLASS B CONC. CY	REINF. STEEL, LEV. I LB	DI GRATE TYPE	TRENCH EX. OF EARTH CY	TRENCH EX. OF ROCK CY	
PEDESTRIAN BRIDGE/ SIDEWALK													
11+63.0	11+67.6	RT	15	12	X	7.1							INSTALL NEW PIPE FROM PROPOSED DI TO CONNECT TO EXISITNG PIPE AT REMOVED DI.
11+63.0		RT									4.9	2.4	REMOVE EXISTING DI, APPROXMATE DEPTH: 4'.
11+67.6		RT					4.5	3.0	211.0	D	7.6		NEW 4X4 RCDI AT STA 11+67.6.
SUBTOTALS:			12.0		7.1		3.0	211.0			12.5	2.4	
ROUNDING			-		-		-	4.0			-	0.6	
TOTALS:			12.0		7.1		3.0	215			12.5	3.0	

CHA

DRAINAGE DETAIL SHEET

PROJECT NAME: JERICHO
PROJECT NUMBER: STP FTBR (3)

PROJECT LEADER: M.D.S.
DESIGNED BY: C.R.H.
DWG. NO.: DDS-1

PLOT DATE: 4/7/2014
DRAWN BY: C.R.H.
CHECKED BY: D.E.G.
SHEET 13 OF 62

FILE NAME = V:\Projects\VNY\K2\21113\CADD\MSTN\06F004\Consultants\r06f004dds.dgn
DATE/TIME = 4/7/2014
USER = 4916