



JERICO-STP FTBR (3)  
CALCULATION PLAN

STRINGER No.	LEN A	GRADE TAN	
		ABUTMENT No.1	ABUTMENT No.2
1	70'-0 $\frac{1}{8}$ "	0.0638	0.0638
2	70'-0 $\frac{1}{8}$ "	0.0638	0.0638

- NO EXCEPTION TAKEN     MAKE CORRECTIONS NOTED  
 REJECTED     REVISE AND RESUBMIT  
 SUBMIT SPECIFIED ITEM

CHECKING IS ONLY FOR GENERAL CONFORMANCE WITH THE DESIGN CONCEPT OF THE PROJECT AND GENERAL COMPLIANCE WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS. ANY ACTION SHOWN IS SUBJECT TO THE REQUIREMENTS OF THE PLANS AND SPECIFICATIONS. CONTRACTOR IS RESPONSIBLE FOR DIMENSIONS WHICH SHALL BE CONFIRMED AND CORRELATED AT THE JOB SITE; FABRICATION PROCESSES AND TECHNIQUES OF CONSTRUCTION; COORDINATION OF HIS WORK WITH THAT OF ALL OTHER TRADES AND THE SATISFACTORY PERFORMANCE OF THE WORK.

DATE 08/07/2014 BY CHA IJS

NOTES:

- THIS DRAWING IS SUBMITTED FOR INFORMATION ONLY, AND IT IS NOT FOR FABRICATION
- ARROW POINTS TOWARDS LOW END OF MEMBER
- TRANSVERSE DIMENSIONS ARE IN HORIZONTAL PLANE U.N.O.
- LONGITUDINAL LENGTHS ARE DEVELOPED
- INTERMEDIATE STIFFENERS ARE NORMAL TO GRADE
- ENDS OF STRINGERS ARE VERTICAL AFTER DL ROTATION

REV.	DATE	ISSUED FOR APPROVAL		By
0	7/22/2014			
MATERIAL: A515TO M270-GR50W U.N.O.		SURFACE PREP. AND PAINT: N/A		SHOP BOLTS: 15/16" U.N.O. 7/8" U.N.O.
DESCRIPTION: CALCULATION PLAN				
CASCO BAY STEEL STRUCTURES, INC. 1 WALLACE AVE. SOUTH PORTLAND, ME 04106 PHONE (207) 780-6722 FAX: (207) 780-6728				
STRUCTURE: VERMONT ROUTE 15 OVER BROWNS RIVER		DRAWN: ID	DATE: 07/22/14	
LOCATION: TOWN OF JERICO, VT		CHECKED: AD	DATE: 07/22/14	
PROJECT NO. STP FTBR (3)		JOB NO. 576	DWG NO. WS1	
CUSTOMER: Blow & Cote, INC.		REV. 0		