

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	RAILROAD	BRIDGE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1		1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
										210	210		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
									1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
										190	190		CY	STRUCTURE EXCAVATION	204.25				
										90	90		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
										225	225		LF	STEEL PILING, HP 14 X 89	505.18				
										3	3		EACH	DYNAMIC PILE LOADING TEST	505.45				
										41640	41640		LB	STRUCTURAL STEEL, PLATE GIRDER	506.55				
										3610	3610		LB	STRUCTURAL STEEL	506.60				
										6	6		GAL	WATER REPELLENT, SILANE	514.10				
										1	1		EACH	REMOVAL OF STRUCTURE (10.25' x 15.58' CONCRETE BOX CULVERT)	529.15				
										2	2		EACH	BEARING DEVICE ASSEMBLY, PLAIN ELASTOMERIC PAD	531.16				
										1	1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT NO. 1)	540.10				
										1	1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT NO. 2)	540.10				
										1	1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB NO. 1)	540.10				
										1	1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB NO. 2)	540.10				
										150	150		CY	STONE FILL, TYPE III	613.12				
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
										130	130		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								45			45		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								10			10		LB	SEED	651.15				
								30			30		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
										100	100		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								48			48		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								10			10		SY	TEMPORARY EROSION MATTING	653.20				
								20			20		CY	VEHICLE TRACKING PAD	653.35				
								1			1		EACH	FILTER BAG	653.45				
								180			180		LF	PROJECT DEMARCATION FENCE	653.55				
										3	3		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)	900.608				
									45		45		CY	SPECIAL PROVISION (RAILROAD BALLAST)	900.608				
									30		30		EACH	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF CROSS TIES)	900.620				
										41	41		LF	SPECIAL PROVISION (RAPID SETTING GROUT)	900.640				
									231		231		LF	SPECIAL PROVISION (REMOVE AND RESET RAILROAD TRACKS)	900.640				
								1			1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645				
										1	1		LS	SPECIAL PROVISION (TIMBER DECK, RAILROAD BRIDGE)	900.645				

N. A. B. I. = NOT A BID ITEM



PROJECT NAME: DORSET  
PROJECT NUMBER: WCRS(8)

FILE NAME: z08g224qs.dgn  
PROJECT LEADER: A.P. GUYETTE  
DESIGNED BY: J.W. GOLEK  
QUANTITY SHEET (1 OF 2)

PLOT DATE: 4/10/2014  
DRAWN BY: J.W. GOLEK  
CHECKED BY: B.O. CRONIN  
SHEET 5 OF 33