DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 2.00 (LB / FT) 2.16	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
LANDGROVE VT 11							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	0	C	VD-024	60	7.5								~~1~~ 0		X														
		C	VD-024	72	10		LANDGROVE | PERU	5.00					1			2		X										4	
		C	VD-700	6	10		0110 0205 0000 / 0110 0207 0463	0.42					1																E-138
		C	VD-700	6	10			0.42					1																E-138
EB	0.061	A	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
EB	0.136	A	W7-3P	24	18		GRADE WARNING						1		X														
		A	W7-1	30	30		PERCENT GRADE PLAQUE						1																
		A	VW-054R	30	30		9%	6.25								1		X											E-154
EB	0.215	A	W7-1b	30	30			6.25								1		X									9% GRADE	X		
EB	0.311	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
EB	0.489	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X														
		C	VR-017	24	30			5.00								1		X									TH-12, LANDGROVE HOLLOW RD			E-141
EB	0.494	D	R1-1	30	30		STOP				~~0~~ 1		~~1~~ 2		X														
		D	R1-1	30	30			6.25				~~0~~ 1				1		X									TH-12, LANDGROVE HOLLOW RD	X		
EB	0.655	A	W1-2R	30	30			6.25								1		X										X		
							SHEET TOTALS	35.84	0.00	0	~~0~~ 1	~~0~~ 1	~~7~~ 10	0	0	7		105											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	72.1	0.0	0.0	0.0	0.0	13	0.0	0.0	13		195.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Manchester-Springfield VT11
PROJECT NUMBER: STPG SIGN(25)

FILE NAME: Landgrove VT11 — PLOT DATE: 4/6/2009
PROJECT MANAGER: N. Avery — DRAWN BY: T. Guazzoni
DESIGNED BY: A. Gamble — CHECKED BY: S. Menard
LANDGROVE SHEET 1 — SHEET 40 OF 115