DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 2.00 (LB / FT) 2.16	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
CHESTER VT11							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	VD-700	6	8		MILE MARKER				~~X~~ 1																		
EB	1.252	C	D1-1A	54	7.5								1		X														
		C	D1-1A	54	7.5								1																
		C	D1-1A	72	12			6.00								2		X								5	
		C	D1-1A	72	12			6.00																		5	
EB	1.254	C	W1-7	48	24								1		X														
		C	W1-7	48	24			8.00								2		X								X	
EB	1.270	A	M3-2	24	12			2.00								1		X								INSTALL 80 FT ± EAST OF (BEYOND) THE DOUBLE ARROW; SIGN IS GREEN ON WHITE SHEETING.	X		
		A	M1-5	24	24			4.00																		GREEN ON WHITE SHEETING			E-136B
EB	1.315	A	W1-2L	36	36		CURVE LEFT						1		X														
			W13-1	18	18		35 MPH (PLAQUE)						1																
EB	1.360	A	W2-2MaL	30	30			6.25								1		X								INSTALL 240 FEET ± EAST OF PREVIOUS SIGN REMOVAL / 5 FEET ± IN ADVANCE OF UTILITY POLE		6	
		A	W16-8	30	18			3.75																		HIDDEN HEIGHTS ROAD (PLAQUE)		6	
EB	1.380	C	VR-017	24	30								1		X														KINGSBURY RD (TH-56)			
		C	VR-017	24	30			5.00								1		X											E-141
							SHEET TOTALS	41.00	0.00	0	~~0~~ 1	0	6	0	0	7		105										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	795.8	0.0	4.0	2.0	2.0	155	0.0	1.0	134		2010.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Manchester-Springfield VT11**
PROJECT NUMBER: **STPG SIGN(25)**

FILE NAME: **Chester VT11.xls** PLOT DATE: **4/8/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
CHESTER SHEET 2 SHEET **78** OF **115**