DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 2.00 (LB / FT) 2.16	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
CHESTER VT11							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	W16-8	30	8			1.67																		PLAQUE	X		
EB	4.048	C	VR-017	24	30								1		X											BLUE HILL ROAD (TH-57)			
		C	VR-017	24	30			5.00								1		X										E-141
EB	4.056	D	R1-1	30	30								1		X											BLUE HILL ROAD (TH-57)			
		D	R1-1	30	30			6.25								1		X									X		
EB	4.135	A	R2-1	24	30			5.00								1		X								INSTALL 125 FT ± IN ADVANCE OF (WEST OF) THE EXISTING SPEED LIMIT 40 SIGN (NEXT ENTRY).	X		
EB	4.160	A	R2-1	24	30		SPEED LIMIT 40						1		X														
EB	4.250	A	R2-5A	24	30		REDUCED SPEED AHEAD						1		X															
		A	W3-5	36	36			9.00								2		X								SPEED REDUCTION 25 AHEAD	X		
EB	4.370	A	R2-1	18	24		SPEED LIMIT 25						1		X														
		A	VR-040	24	24		STATE HIGHWAY ENDS						1																
		B	VR-039	24	18		STATE HIGHWAY BEGINS						1													ON BACK			
		A	VR-038	24	18			3.00								1		X								INSTALL IN TOP POSITION			E-141
		A	R2-1	24	30			5.00																		INSTALL BELOW S.H.E.	X		
WB	4.376	F	R2-1	24	30		SPEED LIMIT 40						1		X														
							SHEET TOTALS	34.92	0.00	0	0	0	8	0	0	6		90											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	795.8	0.0	4.0	2.0	2.0	155	0.0	1.0	134		2010.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Manchester-Springfield VT11**
PROJECT NUMBER: **STPG SIGN(25)**

FILE NAME: **Chester VT11.xls** PLOT DATE: **4/8/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
CHESTER SHEET 6 SHEET **82** OF **115**