DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 2.00 (LB / FT) 2.16	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
CHESTER VT11							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	VR-041	24	24		THROUGH WAY BEGINS HERE						1																
		E	VR-038	24	18		STATE HIGHWAY ENDS						1														ON BACK			
		F	VR-039	24	18		STATE HIGHWAY BEGINS	3.00								1		X								INSTALL IN TOP POSITION			E-141
		F	R2-1	24	30		SPEED LIMIT 40	5.00																		INSTALL BELOW S.H.B.	X		
WB	4.200	F	R2-1	24	30								1		X														
		F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X										X		
WB	4.080	F	VW-054	30	30		HIDDEND DRIVE RIGHT						1		X														
		F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1																
WB	4.045	F	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1		X								INSTALL 185 FT ± WEST OF PREVIOUS REMOVAL. PROVIDE ADDITIONAL OFFSET IF POSSIBLE, DUE TO STEEP SIDEBANK.			E-154
WB	3.870	F	R2-1	24	30								1		X														
		F	R2-1	24	30		SPEED LIMIT 50	5.00								1		X										X		
WB	3.603	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00							1	1		X								RESERVOIR RD (TH-47)			
WB	3.594	H	R1-1	24	24		STOP						1		X											RESERVOIR RD (TH-47)			
		G	VR-017	24	24		LEGAL LOAD LIMIT 24000 POUNDS						1																
		H	R1-1	30	30		STOP	6.25								1		X										X		
							SHEET TOTALS	35.50	0.00	0	0	0	8	0	0 (1)	6		90												
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT												
							TOWN TOTALS	795.8	0.0	4.0	2.0	2.0	155	0.0	1.0	134		2010.0												

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Manchester-Springfield VT11**
PROJECT NUMBER: **STPG SIGN(25)**

FILE NAME: **Chester VT11.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
CHESTER SHEET 7

PLOT DATE: **4/8/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **83** OF **115**