DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 2.00 (LB / FT) 2.16	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
CHESTER VT11							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	6.107	F	VW-619	36	36								1		X														
		F	VW-619	36	36			9.00								2		X										6
WB	6.062	F	VD-062B	72	16		CROW HILL GALLERY OBDS			1				X														
		F	VD-062AS	72	16		HENRY FARM OBDS			1																		
WB	6.017	F	W3-5	36	36								1		X														
		F	W3-5	36	36			9.00								2		X									X	
WB	5.977	F	W1-2R	30	30								1		X														
		F	W1-2R	30	30			6.25								1		X									X	
WB	5.937	F	VW-054	30	30		HIDDEN DRIVE RIGHT						1		X														
		F	VD-700	6	8		MILE MARKER						1														REMOVE MILE MARKER ~ TO BE REPLACED AT LATER DATE			
WB	5.892	F	R2-1	30	36								1		X														
		F	R2-1	30	36			7.50								1		X										6
WB	5.862	F	VW-054	30	30			6.25							1		X									INSTALL 155 FT ± WEST OF SPEED LIMIT 40 SIGN; SIGN WILL BE ON A STEEP SIDESLOPE.			E-154
WB	5.797	F	W2-1Mb	30	30								1		X														
		F	W2-1Mb	30	30			6.25								1		X								PROVIDE ADDITIONAL OFFSET FROM EDGE LINE. IF POSSIBLE, SO AS NOT TO OBSCURE CORNER SIGHT DISTANCE			6
							SHEET TOTALS	44.25	0.00	2	0	0	7	0	0	8		120								
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT								
							TOWN TOTALS	795.8	0.0	4.0	2.0	2.0	155	0.0	1.0	134		2010.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Manchester-Springfield VT11**
PROJECT NUMBER: **STPG SIGN(25)**

FILE NAME: **Chester VT11.xls** PLOT DATE: **4/8/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
CHESTER SHEET 18 SHEET **94** OF **115**