DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 2.00 (LB / FT) 2.16	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SPRINGFIELD VT 11							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
EB	2.450	A	R2-1	30	36		SPEED LIMIT 40					1	1			1		X										
EB	2.457	A	R2-1	30	36		SPEED LIMIT 40				1				X													
EB	2.662	C	VR-017	24	24		LEGAL LOAD LIMIT 24,000 POUNDS						1		X													
		C	VR-017	24	30			5.00								1		X								TH-86, BREEZY HILL RD			E-141
EB	2.670	D	R1-1	30	30		STOP			1				X												TH-86, BREEZY HILL RD			
EB	2.725	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		X									X		
EB	2.760	A	W1-2R	30	30								1		X														
EB	2.825	A	W1-2R	30	30			6.25								1		X								INSTALL 350 FT +/- EAST OF EXISTING	X		
EB	3.185	A	W1-2MhL	30	30		LEFT CURVE INTERSECTION WARNING			1				X															
EB	3.279	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X													
		C	VR-017	24	30			5.00								1		X								TH-96, WALKER RD			E-141
EB	3.287	D	R1-1	30	30		STOP			1				X												TH-96, WALKER RD			
EB	3.359	A	W1-2	30	30		LEFT CURVE			1				X															
EB	3.407	A	W3-5	36	36		SPEED REDUCTION 35			1				X															
EB	3.450	A	VD-018	30	18		SPRINGFIELD	3.75								1		X								10 FT WEST OF LAST POLE BEFORE GUARDRAIL ENDS			E-128A
							SHEET TOTALS	25.00	0.00	5	1	1	4 ~~3~~	0	0	6		90										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	411.7	48.0	26.0	12.0	11.0	74	0.0	0.0	72		1080.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Manchester-Springfield VT-11
PROJECT NUMBER: STPG SIGN(25)

FILE NAME: Springfield VT11.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: J. Kelly
SPRINGFIELD SHEET 2

PLOT DATE: 4/7/2009
DRAWN BY: J. Kelly
CHECKED BY: S. Menard
SHEET 100 OF 115