DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 2.00 (LB / FT) 2.16	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SPRINGFIELD VT 11							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
WB	3.059	G	VR-017	24	30								1		X														
		G	VR-017	24	30			5.00								1		X									TH-27, FAIRGROUND RD			E-141
WB	3.051	H	R1-1	30	30								1		X														
		H	R1-1	30	30			6.25								1		X									TH-27 FAIRGROUND RD	X		
WB	3.050	F	W1-2L	30	30		LEFT CURVE						1		X														
WB	2.980	F	W1-2L	30	30			6.25								1		X									INSTALL 370 FT +/- WEST OF EXISTING SIGN	X		
WB	2.850	F	R2-1	24	30			5.00								1		X									INSTALL AT BEGINNING OF TANGENT AFTER LEFT CURVE, WEST OF DRIVE	X		
WB	2.503	G	VR-017	24	30								1		X														
		G	VR-017	24	30			5.00								1		X									TH-24, BELLOWS RD			E-141
WB	2.511	H	R1-1	30	30						1		1		X														
		H	R1-1	30	30			6.25				1				1		X									TH-24, BELLOWS RD	X		
WB	2.450	F	R2-1	24	30		SPEED LIMIT 50				1	1 1				1		X									PLAN ERROR - RELOCATED			
WB	2.437	F	R2-1	24	30		SPEED LIMIT 50				1				X												INSTALL 70 FT +/- WEST OF EXISTING LOCATION			
WB	2.036	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 LBS			1				X													TH-8, FRENCH MEADOW RD			
WB	2.028	H	R1-1	30	30		STOP				1				X												TH-8, FRENCH MEADOW RD			
							SHEET TOTALS	33.75	0.00	1	4 ~~2~~	3 ~~1~~	5	0	0	7		105											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	411.7	48.0	26.0	12.0	11.0	74	0.0	0.0	72		1080.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Manchester-Springfield VT-11**
PROJECT NUMBER: **STPG SIGN(25)**

FILE NAME: **Springfield VT11.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
SPRINGFIELD SHEET 12

PLOT DATE: **4/7/2009**
DRAWN BY: **J. Kelly**
CHECKED BY: **S. Menard**
SHEET **110** OF **115**