STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (IN)	HEIGHT (IN)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL LB/FT 1.12	2.0	3.0	SQUARE STEEL (IN) LB/FT 1.75	2.0	2.5	1.88	2.42	3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) LB/FT 3.0	4.0	4.0 MOD	1.3	1.7	1.7	FOUND-ATION	TUBULAR STEEL Ø (IN) LB/FT 3.0	3.5	4.0	5.0	7.6	9.0	10.8	14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
OPTION ITEMS																																													
NO. MAIN STREET																																													
113+34, LT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eR * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
113+34, LT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eL * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
113+36, LT	Maple Ave →	1	78	18	9.75																																						MOUNT ON PROPOSED TRAFFIC SIGNAL MAST ARM OVERHEAD STREET NAME SIGN SHS D3-1		E-123
113+57, RT	N. Main St	1	66	18	8.25																																						MOUNT ON PROPOSED TRAFFIC SIGNAL MAST ARM OVERHEAD STREET NAME SIGN SHS D3-1		E-123
114+42, LT	N. Main St	1	66	18	8.25																																						MOUNT ON PROPOSED TRAFFIC SIGNAL MAST ARM OVERHEAD STREET NAME SIGN SHS D3-1		E-123
114+49, RT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eR * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
114+49, RT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eL * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
114+50, LT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eR * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
114+50, LT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eL * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
VT ROUTE 62																																													
10+39, LT	← Maple Ave	1	78	18	9.75																																						MOUNT ON PROPOSED TRAFFIC SIGNAL MAST ARM OVERHEAD STREET NAME SIGN SHS D3-1		E-123
10+63, RT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eR * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
10+63, RT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eL * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
NO. MAIN STREET																																													
138+73, RT	N. Main St	1	30	12	2.50																																						STANDARD STREET NAME SIGN MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS D3-1		E-123
138+73, RT	N. Main St	1	30	12	2.50																																						STANDARD STREET NAME SIGN MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS D3-1		E-123
138+68, LT		1	9	15	*																																						MOUNT ON PROPOSED TRAFFIC SIGNAL POLE SHS R10-3eR * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
139+02, LT	← Washington St N. Main St →	1	84	36		21.00																																					MOUNT ON PROPOSED TRAFFIC SIGNAL STRUCTURE OVERHEAD STREET NAME SIGN SHS D3-1		E-123
												FT	FT	FT	FT	FT	FT			EA	LB	LB	LB			LB	LB	LB	LB											
		TOTALS			SF 41.00	SF 21.00	EA.	SF				FT			FT							LB			EA.			LB					EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

AVERAGE POST LENGTH = 15 FT

VHB Vanasse Hangen Brustlin, Inc.

PROJECT NAME:	BARRE CITY
PROJECT NUMBER:	FEGC F 026-1(34) C/1
FILE NAME: z09B240_TSSS.dgn	PLOT DATE: 4/5/2010
PROJECT LEADER: G. BAKOS	DRAWN BY: DMP / JAR
DESIGNED BY: DMP / MDS	CHECKED BY:
TRAFFIC SIGN SUMMARY SHEET 1	SHEET 41 OF 95