STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (IN)	HEIGHT (IN)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL LB/FT 1.12	2.0	3.0	SQUARE STEEL (IN) 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) LB/FT 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (IN) FOUND-ATION	LB/FT 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
SUMMER STREET																																			
400+51, LT		1	9	15	*																												SHS R10-3eL MOUNT ON PROPOSED TRAFFIC PEDESTAL POLE * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
400+52, RT		1	9	15	*																												SHS R10-3eR MOUNT ON PROPOSED TRAFFIC PEDESTAL POLE * PAID UNDER TRAFFIC CONTROL SIGNAL ITEMS		
400+91, LT	TO 302	1 1 1	24 30 21	12 24 15	2.00 5.00 2.19						1						X															#2	SHS M4-5 MOUNT ON 1 #2 FRAME SHS M1-4 SHS M6-1		E-136A
400+91, LT	NORTH VERMONT 14	1 1 1	24 24 21	12 24 15	2.00 4.00 2.19						1						X																SHS M3-1 MOUNT ON 1 #2 FRAME SHS M1-5VT SHS M6-1		E-136B
400+92, RT	NO PARKING ANY TIME	1	12	18	1.50						1						X																SHS R7-1		E-143
400+94, LT	NO PARKING ANY TIME	1	12	18	1.50						1						X																SHS R7-1		E-143
401+43, RT	NO PARKING ANY TIME	1	12	18	1.50						1						X																SHS R7-1		E-143
402+00, LT	ONLY ONLY	1	36	30	7.50						2						X																VR-925		E-145A
402+08, RT	NO PARKING ANY TIME	1	12	18	1.50						1						X																SHS R7-1		E-143
422+20, LT	TO NORTH VERMONT 14	1 1 1 1	24 24 24 21	12 12 24 15	2.00 2.00 4.00 2.19						1						X																SHS M4-5 SHS M3-1 SHS M1-5 (VT) SHS M6-1		E-136B

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

AVERAGE POST LENGTH = 15 FT

	SF	SF	EA.	SF		FT	FT	LB	EA.	LB	EA.	EA.	LB
						FT	FT 135	LB		LB			
TOTAL SHEET 5	41.07	0	0										
TOTAL SHEET 4	68.38	0	0				150						
TOTAL SHEET 3	66.13	0	0				165						
TOTAL SHEET 2	53.00	63.00	0				0						
TOTAL SHEET 1	41.00	21.00	0				0						
TOTAL ALL SHEETS	269.58	84.00	0				450						

VHB Vanasse Hangen Brustlin, Inc.

PROJECT NAME:	BARRE CITY
PROJECT NUMBER:	FEGC F 026-1(34) C/1
FILE NAME: z09B240_TSSS.dgn	PLOT DATE: 4/5/2010
PROJECT LEADER: G. BAKOS	DRAWN BY: DMP / JAR
DESIGNED BY: DMP / MDS	CHECKED BY:
TRAFFIC SIGN SUMMARY SHEET 5	SHEET 45 OF 95