DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
HARTFORD VT 14							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.981	D	R1-1	30	30		STOP			1				X															
NB	6.982	A	R2-1	24	30		SPEED LIMIT 35			1				X															
NB	7.216	A	R2-1	24	30		SPEED LIMIT 35			1				X															
NB	7.256	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X												TIGER TOWN RD TH-13		
		C	VR-017	24	30			5.00								1		X											E-141
NB	7.262	D	R1-1	30	30		STOP			X				X													TIGER TOWN RD TH-13		
NB	7.437	A	R2-1	24	30		SPEED LIMIT 50 MPH				1				X												SALVAGE TO 7.530 NB		
NB	7.500	A	W1-2L	30	30		LEFT CURVE				1				X												SALVAGE TO 7.590 NB		
		A	W13-1	18	18		40 MPH PLAQUE				1																		
NB	7.530	A	R2-1	24	30		SPEED LIMIT 50 MPH					1				1		X									INSTALL 0.28 MILES (1478') NORTH OF INTERSECTION TIGER TOWN RD. TH-13 SALVAGE FROM 7.437 NB		
NB	7.590	A	W1-2L	30	30		LEFT CURVE					1				1		X									INSTAL L 475' +/- NORTH OF ORIGINAL LOCATION		
		A	W13-1	18	18		40 MPH PLAQUE					1															SALVAGE FROM 7.500 NB		
NB	7.632	A	W1-6	48	24								1	X															
		A	W1-6	48	24			8.00								2												X	
NB	7.665	B	W1-6	48	24								1	X															
							SHEET TOTALS	13.00	0.00	~~4~~ 3	3	3	3	0	0	~~5~~ 3	45												
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT												
							TOWN TOTALS	130.2	0.0	41.0	13.0	9.0	26	0.0	0.0	26	390.0												

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Hartford-East Montpelier VT14**
PROJECT NUMBER: **STPG SIGN(21)**

FILE NAME: **Hartford.xls** PLOT DATE: **6/10/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **D. Crossley** CHECKED BY: **S. Menard**
HARTFORD SHEET 4 SHEET **11** OF **162**