DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
HARTFORD VT 14							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W16-8A	24	8		Runnals Rd	1.33																				7	
SB	2.144	G	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS						0 ~~1~~		0 ~~X~~											NO EXISTING			
		G	VR-023B	24	30			5.00								1		X											E-144
SB	1.603	F	W3-5	36	36		SPEED REDUCTION AHEAD SPEED LIMIT 30			1				X															
SB	1.533	F	VD-018	30	18		HARTFORD White River Jct 1	3.75								1		X								INSTALL ACROSS FROM VT 14 SIGN			E-128B
SB	1.477	F	VR-038	24	18		STATE HIGHWAY ENDS			1				X															
		F	R2-1	24	30		SPEED LIMIT 30			1																			
							SHEET TOTALS	10.08	0.00	3	0	0	0 ~~1~~	0	0	2		30											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	130.2	0.0	41.0	13.0	9.0	26	0.0	0.0	26		390.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Hartford-East Montpelier VT14
PROJECT NUMBER: STPG SIGN(21)

FILE NAME: Hartford.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: D. Crossley
HARTFORD SHEET 8

PLOT DATE: 6/10/2009
DRAWN BY: I. Shea
CHECKED BY: S. Menard