DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
RANDOLPH VT 14							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	5.346	A	R2-1	24	30		SPEED LIMIT 50 MPH			1				X															
NB	5.380	A	W5-2	30	30			6.25								1		X								INSTALL 150'+/- NORTH OF SPEED LIMIT 50	X		
NB	5.415	A	OM-3R	12	36		RIGHT OBJECT MARKER				1				X														
NB	5.410	A	OM-3R	12	36		RIGHT OBJECT MARKER					1				1		X											
NB	5.420	B	OM-3L	12	36		LEFT OBJECT MARKER				1	1			X	1		X											
NB	5.900	A	W11-6	30	30		SNOWMOBILE SYMBOL						1		X														
NB	6.290	A	W5-2	30	30			6.25								1		X								INSTALL 150' NORTH OF DRIVEWAY #1334	X		
NB	6.365	A	OM-3R	12	36								1		X														
		A	OM-3R	12	36			3.00								1		X									X		
NB	6.385	B	OM-3L	12	36			3.00					1			1		X								INSTALL AT NORTH END OF BRIDGE 38	X		
NB	6.670	A	W1-2R	30	30		RIGHT CURVE						1		X														
		A	W13-1	18	18		35 MPH PLAQUE						1																
NB	6.690	A	W1-2R	30	30			6.25								1		X								INSTALL 130' +/- NORTH OF ORIGINAL SIGN LOCATION	X		
		A	W13-1	18	18			2.25																			X		
NB	6.698	C	VR-017	24	24								0 ~~1~~		X														
SIGN SUMMARY SHEET							SHEET TOTALS	27.00 SF	0.00 SF	1 EA	2 EA	2 EA	5 EA	0 EA	0 EA	7 EA	105 FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	771.4	0.0	19.0	5.0	5.0	155	0.0	0.0	130	1950.0											

PROJECT NAME: **Hartford-East Montpelier VT14**
PROJECT NUMBER: **STPG SIGN(25)**

FILE NAME: **Randolph.xls** PLOT DATE: **6/18/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **D. Crossley** CHECKED BY: **S. Menard**
RANDOLPH SHEET 11 SHEET **74** OF **162**