DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
BROOKFIELD VT 14							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.570	A	W1-2R	30	30		CURVE RIGHT						1		X														
		A	W13-1	24	24		35 MPH PLAQUE						1																
SB	5.940	F	VW-054L	30	30		HIDDEN DRIVE LEFT						1		X														
SB	5.930	F	VW-054L	30	30			6.25								1		X									INSTALL 100' +/- SOUTH OF ORIGINAL LOCATION			E-154
SB	4.395	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X									TWIN POND RD TH-12			E-141
SB	4.380	H	R1-1	30	30		STOP	6.25								1		X										X		
SB	3.880	F	M2-1	21	15								1		X														
		F	M1-5	24	24		JCT						1																
		F	M2-1	21	15		VERMONT 65	2.19								1		X									GREEN ON WHITE SHEETING	X		
		F	M1-5	24	24			4.00																					E-136B
SB	3.870	F	W11-5	30	30			6.25								1		X									INSTALL 200' SOUTH OF ROUTE MARKER ASSEMBLY	X		
		F	W7-3A	24	18		NEXT 4 MILES	3.00																			NEW STOLEN	X		
SB	3.800	F	VD-062A	72	16		BUSINESS SIGN			1				X															
SB	3.780	F	VD-018	30	18		EAST BROOKFIELD NORTH RANDOLPH 4	3.75								1		X											E-128B
SB	3.764	F	R2-1	24	30								1		X														
							SHEET TOTALS	~~36.69~~ 42.94 SF	0.00 SF	1 EA	0 EA	0 EA	6 EA	0 EA	0 EA	6 EA	90 FT												
							TOWN TOTALS	332.4 SF	0.0 SF	2.0 EA	0.0 EA	0.0 EA	50 EA	0.0 EA	0.0 EA	49 EA	735.0 FT												

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Hartford-East Montpelier VT14
PROJECT NUMBER: STPG SIGN(21)

FILE NAME: Brookfield.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: D. Crossley
BROOKFIELD SHEET 5

PLOT DATE: 6/10/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard
SHEET 92 OF 162