DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WILLIAMSTOWN VT 14							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	M3-3S	24	12		SOUTH			1																		
		F	M1-5	24	24		VT 14			1																		
		F	M6-3S	21	15		UP ARROW			1																		
		F	M4-5I	24	12		TO			1																		
		F	M1-1	24	24		I-89			1																		
		F	M6-1	21	15		RIGHT ARROW			1																		
		F	M3-4S	24	12		WEST			1																		
		F	M1-5	24	24		VT 64			1																		
		F	M6-1S	21	15		RIGHT ARROW			1																		
SB	4.510	F	VR-345	24	30		NO PARKING HERE TO CORNER						1		X													
		F	R8-3A	24	24			4.00								1		X								X		
		F	R8-3cM	24	18			3.00																			5	
SB	4.470	F	R2-1	24	30								1		X													
		F	R2-1	24	30			5.00								1		X								X		
SB	4.450	F	M3-3	24	12								1		X													
							SHEET TOTALS	12.00	0.00	9	0	0	3	0	0	2		30										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	501.1	0.0	67.0	0.0	0.0	94	0.0	0.0	109		1635.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Hartford-East Montpelier VT14
PROJECT NUMBER: SIGN STPG(21)

FILE NAME: Williamstown.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: A. Gamble
WILLIAMSTOWN SHEET 12

PLOT DATE: 6/18/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard