DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BARRE TOWN VT 14							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
NB	0.000	C	VD-024	60	7.5								1		X														
		C	VD-025	60	7.5								1																
		C	VD-025	72	10			5.00								2		X										4	
		C	VD-024	72	10		BARRE TOWN | WILLIAMSTOWN WASHINGTON CO | ORANGE CO 0140 1202 0000 | 0140 0917 0683	5.00																				4	
		C	VD-700	6	10			0.42																			BARRE TOWN MILE MARKER ~ INSTALL ON LEFT POST			E-138
		C	VD-700	6	10			0.42																			WILLIAMSTOWN MILE MARKER ~ INSTALL ON RIGHT POST			E-138
NB	0.035	C	VR-017	24	24		LEGAL LOAD LIMIT 24000 LBS			1				X													TH-124, KINGS ROW			
NB	0.040	D	R1-1	24	24		STOP			1				X													TH-124, KINGS ROW			
NB	0.115	C	VR-017	24	24		LEGAL LOAD LIMIT 24000 LBS			1				X													TH-130, MORIN RD			
NB	0.120	D	R1-1	24	24		STOP			1				X													TH-130, MORIN RD			
NB	0.165	C	VR-017	24	24		LEGAL LOAD LIMIT 24000 LBS			1				X													TH-167, LEO AVE			
NB	0.170	D	R1-1	24	24		STOP			1				X													TH-167, LEO AVE			
NB	0.200	A	R2-1	24	30		SPEED LIMIT 40			1				X																
NB	0.800	C	VR-017	24	24		LEGAL LOAD LIMIT 24000 LBS			1				X													TH-104, JACKSON ST			
NB	0.805	D	R1-1	24	24		STOP			1				X													TH-104, JACKSON ST			
SIGN SUMMARY SHEET							SHEET TOTALS	10.84	0.00	9	0	0	2	0	0	2		30										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	583.8	0.0	48.0	9.0	9.0	115	0.0	0.0	89		1335.0										

PROJECT NAME: **Hartford-East Montpelier VT14**
PROJECT NUMBER: **STPG SIGN(21)**

FILE NAME: **Barre Town.xls** PLOT DATE: **6/18/2009**
PROJECT MANAGER: **N. Averv** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **A. Gamble** CHECKED BY: **S. Menard**
BARRE TOWN SHEET 1 SHEET **115** OF **162**