DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
E MONTPELIER VT 14							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		B	W1-8R	18	24								1		X														
		A	W1-8L	24	30	FY		5.00								1		X									INSTALL ON SEPARATE POSTS 5 FEET APART	X		
		B	W1-8R	24	30	FY		5.00								1		X										X		
NB	1.680	A	W3-5	36	36			9.00					1		X	2		X									EXISTING SIGN REMOVED INSTALL 50 FT +/- NORTH OF GRAVEL PULLOFF	X		
NB	1.800	A	R2-1	24	30								1		X														
		A	R2-1	30	36			7.50								1		X										6		
NB	1.960	A	R2-1	24	30		SPEED LIMIT 35			~~0~~ 1			1	~~X~~	X														
NB	2.010	A	W11-7	30	30								1		X														
		A	W11-7	30	30			6.25								1		X										X		
NB	2.035	C	VR-017	24	30						2		1		X												REMOVED MM PLAQUE REMOVED STREET SIGN			
		C	VR-017	24	30			~~6.25~~ 5.00								1		X								2 SIGNS SALVAGED FROM NB 2.035 TH-43, CARLTON BLVD			E-141
NB	2.040	D	R1-1	30	30							2	1		X														
		D	R1-1	30	30			6.25								1		X								TH-43, CARLTON BLVD	X		
NB	2.080	A	W1-2L	30	30		LEFT CURVE						1		X														
NB	2.135	A	W1-2L	30	30			6.25								1		X									INSTALL 300 FT +/- NORTH OF EXISTING	X		
SIGN SUMMARY SHEET							SHEET TOTALS	~~51.50~~ 50.25 SF	0.00 SF	~~1~~ 0 EA	~~0~~ 2 EA	~~0~~ 2 EA	~~6~~ 8 EA	0 EA	0 EA	9 EA		135 FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	803.2	0.0	27.0	3.0	3.0	149	0.0	0.0	132		1980.0										

PROJECT NAME: Hartford-East Montpelier VT14
PROJECT NUMBER: STPG SIGN(21)

FILE NAME: East Montpelier.xls
PROJECT MANAGER: N. Averv
DESIGNED BY: M. Miller
EAST MONTPELIER SHEET 4

PLOT DATE: 6/18/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard
SHEET 139 OF 162