| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **E MONTPELIER VT 14** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| | | A | D1-1 | 72 | 12 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | D2-1 | 72 | 12 | | EAST CALAIS 5 | 6.00 | | | | | | | | 2 | | X | | | | | | | | | | 5 | |
| | | A | D2-1 | 72 | 12 | | WOODBURY 11 | 6.00 | | | | | | | | | | | | | | | | | | | | 5 | |
| NB | 5.640 | A | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | SPEED LIMIT 35 | 5.00 | | | | | | | | 1 | | X | | | | | | | | | | X | |
| SB | 5.820 | A | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | R2-1 | 30 | 36 | | SPEED LIMIT 35 | 7.50 | | | | | | | | 1 | | X | | | | | | | | | | 6 | |
| SB | 5.780 | F | W11-2 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | F | W11-2 | 30 | 30 | FYG | | 6.25 | | | | | | | | 1 | | X | | | | | | | | | | X | |
| SB | 5.730 | F | VD-018 | 30 | 18 | | NORTH MONTPELIER<br>EAST MONTPELIER 3 | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | F | VD-018 | 30 | 18 | | | 3.75 | | | | | | | | 1 | | X | | | | | | | | | | | E-128A |
| SB | 5.685 | F | M2-1 | 21 | 15 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | F | M1-5 | 24 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | M2-1 | 21 | 15 | | JCT VERMONT 214 | 2.19 | | | | | | | | 1 | | X | | | | | | | | | GREEN ON WHITE SHEETING | X | | |
| | | F | M1-5 | 30 | 24 | | | 5.00 | | | | | | | | | | | | | | | | | | | | | E-136B |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 41.69 | 0.00 | 0 | 0 | 0 | 7 | 0 | 0 | 7 | 105 | | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | | | | | | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN TOTALS | 803.2 | 0.0 | 27.0 | 3.0 | 3.0 | 149 | 0.0 | 0.0 | 132 | 1980.0 | | | | | | | | | | | |

PROJECT NAME: Hartford-East Montpelier VT14
PROJECT NUMBER: STPG SIGN(21)

FILE NAME: East Montpelier.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: M. Miller
EAST MONTPELIER SHEET 13

PLOT DATE: 6/18/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard