| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND<br>FOR ALL POST LENGTHS AND INSTALLATION DATES SEE ORIGINAL RECORD PLANS | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL IN SHS | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **E MONTPELIER VT 14** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| SB | 2.820 | F | VD-018 | 30 | 18 | | VILLAGE SIGN | | | 1 | | | | X | | | | | | | | | | | | | | |
| SB | 2.740 | F | R2-1 | 24 | 30 | | | | | | 1 | | 1 | | X | | | | | | | | | | | | | | |
| | | F | R2-1 | 30 | 36 | | | 7.50 | | | | 1 | | | | 1 | | X | | | | | | | | | | 6 |
| SB | 2.690 | F | W11-2 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | W11-8 | 30 | 30 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | F | W11-2 | 30 | 30 | FY | | 6.25 | | | | | | | | ~~2~~ 1 | | X | | | | | | | | X | |
| | | F | W11-8 | 30 | 30 | FY | | 6.25 | | | | | | | | | | | | | | | | | | X | |
| SB | 2.650 | F | VD-062B | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | F | VD-062A | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | | | | | | | | | | | | | | | |
| SB | 2.610 | F | W11-2 | 30 | 30 | | PEDESTRIAN SYMBOL | | | | | | 1 | | X | | | | | | | | | | | | | |
| SB | 2.590 | F | M2-1 | 21 | 15 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | M1-4 | 24 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | F | M2-1 | 21 | 15 | | | 2.19 | | | | | | | | 1 | X | | | | | | | X | |
| | | F | M1-4 | 24 | 24 | | | 4.00 | | | | | | | | | | | | | | | | | | X | |
| SB | 2.585 | G | VR-017 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 26.19 SF | 0.00 SF | 3 EA | ~~1~~ 0 EA | ~~1~~ 0 EA | 7 EA | 0 EA | 0 EA | ~~3~~ 4 EA | 60 FT | | | | | | | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN TOTALS | 803.2 | 0.0 | 27.0 | 3.0 | 3.0 | 149 | 0.0 | 0.0 | 132 | 1980.0 | | | | | | | | | | | |

PROJECT NAME: Hartford-East Montpelier VT14
PROJECT NUMBER: STPG SIGN(21)
FILE NAME: East Montpelier.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: M. Miller
PLOT DATE: 6/18/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard
EAST MONTPELIER SHEET 18
SHEET 153 OF 162