

TOWN TOTAL SIGN SUMMARY SHEET

VT ROUTE 14 Hartford - East Montpelier STPG SIGN (21)

Townname	County	Town Mileage	NEW SIGNS (SF)		EXISTING SIGNS (EA)				EXIST POST (EA)		NUMBER OF NEW POSTS (EA)			SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					
			TYPE A	TYPE B	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE	1.75"	2"	2.5"	TOTAL POSTS	1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00	5.00
											(LB / FT)				(LB / FT)				(LB / FT)			
											1.88	2.42	3.35		1.88	2.42	3.35		7.60	9.00	10.80	14.60
Hartford	Windsor	7.856	130.20	0	41	13	9	26	0	0	0	26	0	390.00	0							
Sharon	Windsor	7.565	447.00	0	11	1	1	93	0	0	0	64	0	960.00	0							
Royalton	Windsor	9.121	973.50	0	62	9	9	190	0	0	0	152	0	2280.00	0							
Bethel	Windsor	0.89	99.80	0	0	0	0	20	0	0	0	17	0	255.00	0							
Randolph	Orange	7.734	771.40	0	19	5	5	155	0	0	0	128	2	1920.00	30							
Brookfield	Orange	6.677	332.40	0	2	0	0	50	0	0	0	45	4	675.00	60							
Williamstown	Orange	6.833	501.10	0	67	0	0	94	0	0	28	81	0	1215.00	0							
Barre (Town)	Washington	4.033	583.80	0	48	9	9	115	0	0	0	89	0	1335.00	0							
East Montpelier	Washington	5.821	803.20	0	27	3	3	149	0	0	6	120	6	1800.00	90							
Sub-Total						40	36	892						510	10830	180						
Estimated Salvaged Street Name Signs to be erected onto new posts =																						
Salvaged From signs to be added to Remove total =																						
TOTAL =			4642.4	0	277	40	61	932	0	0	34	722	12	768	510	10830	180	0	0	0	0	

SEE ADDITIONAL PAGE, THIS SHEET, FOR ACTUAL TOWN TOTALS.

PROJECT NAME: HARTFORD - EAST MONTPELIER
PROJECT NUMBER: STPG SIGN (21)

FILE NAME: 09c024_TS.DGN	PLOT DATE: 23-JUN-2009
PROJECT LEADER: N. AVERY	DRAWN BY: N. AVERY
DESIGNED BY: N. AVERY	CHECKED BY: A. GAMBLE
TOWN TOTAL SIGN SUMMARY SHEET	SHEET 160 OF 162