DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TUNBRIDGE VT 110							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHS"-STANDARD HIGHWAY SIGNS			
SB	5.640	F	VD-018	30	18								1		X													
		F	VD-018	30	18			3.75								1		X										E-128B
SB	5.610	F	W1-2L	30	30			6.25								1		X							INSTALL 150' +/- SOUTH OF NORTH TUNBRIDGE SIGN	X		
		F	W13-1	24	24			4.00																		X		
SB	5.550	F	R2-1	24	30								1		X													
		F	R2-1	30	36			7.50								1		X								X		
SB	5.440	F	W1-2R	30	30		CURVE RIGHT						1		X													
SB	5.370	F	R2-1	24	30								1		X		X											
		F	R2-1	30	36			7.50								1		X									6	
SB	5.350	F	W1-2R	30	30			6.25								1	X	X							INSTALL 75' +/- SOUTH OF UTILITY POLES, AND 80' +/- NORTH OF BEGINNING OF CURVE	X		
SB	5.262	F	W16-9YG	24	12		SCHOOL			1				X											W/FLASHING BEACON			
		F	S1-1YG	30	30		AHEAD			1																		
SB	5.230	F	VW-054R	30	30								1		X													
		F	VW-054R	30	30			6.25								1		X										E-154
SB	5.180	H	R1-1	24	24		STOP			1				X														
							SHEET TOTALS	41.50	0.00	3	0	0	5	0	0	6		90										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	743.6	0.0	47.0	7.0	7.0	122	0.0	0.0	133		1995.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Royalton-Barre Town VT110
PROJECT NUMBER: STPG SIGN(23)

FILE NAME: Tunbridge.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: D. Crossley
TUNBRIDGE SHEET 15

PLOT DATE: 6/16/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard
SHEET 28 OF 80