DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
WASHINGTON VT 110							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.110	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
		A	W13-1	24	24		35 MPH PLAQUE						1																
NB	1.130	A	W1-4R	30	30			6.25								1		X								INSTALL 100'+/- NORTH OF ORIGINAL SIGN LOCATION	X		
NB	1.395	A	OM-3R	12	36		VERTICAL OBJECT MARKER						1		X														
NB	1.405	B	OM-3L	12	36		VERTICAL OBJECT MARKER						1		X														
NB	1.661	C	VR-017	24	30								1		X											SKY ACRES RD TH-29			
		C	VR-017	24	30			5.00								1		X											E-141
NB	1.669	D	R1-1	30	30								1		X											SKY ACRES RD TH-29			
		D	R1-1	30	30			6.25								1		X									X		
NB	1.782	A	OM-3R	12	36								1		X														
		A	OM-3R	12	36			3.00								1		X									X		
NB	1.790	B	OM-3L	12	36								1		X														
		B	OM-3L	12	36			3.00								1		X									X		
NB	2.347	A	OM-3R	12	36		VERTICAL OBJECT MARKER						1		X														
NB	2.353	B	OM-3L	12	36		VERTICAL OBJECT MARKER						1		X														
							SHEET TOTALS	23.50	0.00	0	0	0	10	0	0	5		75											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	320.1	0.0	42.0	3.0	3.0	66	2.0	0.0	73		1095.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Royalton-Barre Town VT110
PROJECT NUMBER: STPG SIGN(23)
FILE NAME: Washington.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: D. Crossley
WASHINGTON SHEET 2
PLOT DATE: 6/15/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard
SHEET 55 OF 80